

State of Kansas



15-009-20032-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 30 1967
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Dale Oller of Murfin Drilling Co. has this date requested permission to plug the following described well:

Mr. Vincent F. Hiebsch guarantees payment of the plugging fee.

Operator's full Name: Vincent F. Hiebsch

Complete Address: 1015 Central Bldg., Wichita, Kansas

Lease Name: Ahrens Well No. # 1

Location: NW SW NE Sec. 20 Twp. 16 Rge. 12 (E) (W) X

County Barton Total Depth 3420 Oil Well 1

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dale Oller was instructed to plug the well as follows:

8 5/8" 368' Cwc.

Filled hole with heavy mud to 600', set plug, & displaced 20 sax cement thru drill pipe. Mud to 350', set plug with 1/4 sax hulls, & displaced 20 sax cement thru drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax cement, cementing to base of cellar.

Very truly yours,

Dale Oller
Conservation Division Agent