



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Towns of Mustang Drlg. Inc. has this date requested permission to plug the following described well:

Mr. Towns guarantees payment of the plugging fee.

Operator's full Name: Mustang Drlg., Inc.

Complete Address: Box 1425 Great Bend, Ks. 67530

Lease Name: Dwyer Well No. #1

Location: 1080' FEL. & 1220' EMI Sec. 6 Twp. 21 Rge. 14 (E)(W) X

County: Stafford Total Depth 3750 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Towns was instructed to plug the well as follows:

912' 8 5/8" casing comont w/25 sx. 50/50 poz-mix

2% gel 3% c.c follow w/175 sx. c.cement 2% gel

3% c.c plug & 50 sx. @ 910' plug & 40 sx. @ 400'

Bridge & 10 sx. @ 40' to 5' below g.l.

2 sx. cement in w.w. 15 sx in rathole

Cemented by Sun

Very truly yours,

M. V. Lusli
Conservation Division Agent

2-3-81
RECEIVED
FEB - 5 1981
CONSERVATION DIVISION
WICHITA, KANSAS