

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 24 Twp. 21S Rge. (E) 14 (W)
Location as "NE/CNW/SW" or footage from lines SE NW NE
Lease Owner Circle Oil Company, Inc.
Lease Name BORDEWICK Well No. 1
Office Address 500 Bitting Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 3, 19 67
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced February 3, 19 67
Plugging completed February 3, 19 67
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Archie Elving)

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3732 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	247'	8-5/8"	1/28/67	-----
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 225 feet; 1/2 sack Hulls, Plug and 25 sacks Cement thru the Drill Pipe; Mud to 40 feet; 1/2 sack Hulls, Plug and 10 sacks Cement to Base of Cellar; 2 sacks cement in Rat Hole. Job completed at 12:15 P.M.

RECEIVED
FEB 9 1967
NATIONAL DIVISION
2-9-67

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sage Drilling Co., Inc.
Address 500 Bitting Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Lawrence F. Gray (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lawrence F. Gray
500 Bitting Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 7th day of February, 19 67

Louise K. Whitted
Louise K. Whitted - Notary Public.

My commission expires November 26, 1970.

DRILLERS LOG

BORDEWICK NO. 1

CASING RECORD:	COMPANY: Circle Oil Co., Inc.	DESCRIPTION:
8-5/8" @ 247' w/250 sax cement	CONTRACTOR: Sage Drilling Co.	SE NW NE Sec. 24-21S-14W Stafford Co., Kansas
TOTAL DEPTH: 3732'	COMMENCED: January 28, 1967	ELEVATION: 1930KB
	COMPLETED: February 3, 1967	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Top Soil		15	
Sand	15	145	
Shale	145	248	
Shale & Red Bed	248	812	
Anhydrite	812	837	
Shale	837	1215	
Shale & Sandy Lime	1215	1645	
Lime & Shale	1645	2175	
Shale & Lime	2175	2951	
Lime & Shale	2951	3287	
Shale	3287	3366	
Lime & Shale	3366	3485	
Lime	3485	3590	
Lime & Shale	3590	3668	
Shale	3668	3717	
Lime	3717	3732	

RECEIVED
STATE CORPORATION COMMISSION
FEB 9 1967
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Lawrence F. Gray
Lawrence F. Gray

Subscribed and sworn to before me this 7th day of February, 1967.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.