


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Flat

Stafford County. Sec. 23 Twp. 21 Rge. 14 (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SW NE
Lease Owner Petroleum, Inc.
Lease Name Bordewick Well No. I
Office Address 100 Derby Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 22, 19 50
Application for plugging filed October 30, 19 50
Application for plugging approved October 25, 19 50
Plugging commenced October 22, 19 50
Plugging completed October 22, 19 50
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 3778 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	235'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 255'. Placed wooden plug at 255' and cemented with 15 sax cement.

Filled hole with heavy mud to 30'. Placed plug at 30' and cemented to surface.

RECEIVED
STATE CORPORATION COMMISSION
OCT 31 1956

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Petroleum, Inc. CONSERVATION DIVISION
Address 100 Derby Building, Wichita, Kansas Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Woody W. Fisher (employee of owner or owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Woody W Fisher
100 Derby Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of October, 19 50

Charlotte Heidman
Notary Public.

My commission expires October 13, 1954

PLUGGING
FILE SEC 23 T 21 R 14W
BOOK PAGE 38 LINE 17

WELL LOG BORDEWICK #1

Petroleum, Inc., Lease Owner

Section 23, Twp. 21S, Rge. 14W

Garvey Oil, Contractor

Location: SE SW NE

Rotary Total Depth: 3778'

County: Stafford, Kansas

Commenced: October 10, 1950

Elevation: 1931 D.F.

Completed: October 21, 1950

Casing: 8 5/8" x 235'

Figures below indicate bottom of formation:

25 Surface Clay
 180 Sand & Gravel
 235 Shale & Shells
 335 Sand
 340 Shale & Shells
 350 Shale
 835 Red Bed
 860 Anhydrite
 1175 Shale & Shells
 1855 Lime & Shale
 3130 Lime
 3320 Lime & Shale
 3402 Lime
 3685 Chert
 3693 Shale
 3758 Lims

Tops:

835 Anhydrite
 3256 Heebner
 3279 Toronto
 3294 Base Oread
 3374 Br. Lime
 3386 Lansing
 3602 B.K.C.
 3640 Viola
 3684 Simpson
 3728 Arbuckle

3386
 1931
 -1455

3778 R.T.D.

D & A

D.S.T. #1, 3390-3420, open 1 hour, week 20
 blow, rec. 95' mud with rainbow
 show of oil
 D.S.T. #2, 3490-3516, open 1 hour, rec. 60'
 mud
 D.S.T. #3, 3566-93, open 1 hour, rec. 30'
 slightly oil cut mud

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

Eric H. Jager
 Eric H. Jager

STATE OF KANSAS:
 : SS.
 SEDGWICK COUNTY:

Subscribed to and sworn to before me, a Notary Public in said County and State this 24th day of October, 1950.

Charlotte H. ...
 STATE NOTARY PUBLIC COMMISSION

My commission expires: October 13, 1954

PLUGGING
 FILE SEC 23 T 21 R (4)
 BOOK PAGE 38 LINE 7

OCT 31 1950
 CONSERVATION DIVISION
 Wichita, Kansas

RECEIVED
MAY 10 1962
U.S. AIR FORCE
OFFICE OF THE
SECRETARY

RECEIVED
MAY 10 1962
U.S. AIR FORCE
OFFICE OF THE
SECRETARY

[Faint, mostly illegible text, possibly a letter or report, covering the majority of the page.]