

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15.185.21074.0000

API NUMBER ?

LEASE NAME Strobel

WELL NUMBER 1

SPOT LOCATION NW NE NW

SEC. 23 TWP. 21 RGE. 11 (\*) or (W)

COUNTY Stafford

Date Well Completed 6-28-80

Plugging Commenced 12-26-81

Plugging Completed 1-3-85

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Frank J. Black

ADDRESS Box 250, McPherson, Kansas 67160

PHONE # (316) 241-2621 OPERATORS LICENSE NO. \_\_\_\_\_

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District Dodge City

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation Lansing Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 07 1985  
CONSERVATION DIVISION  
Wichita, Kansas

Formation	Content	From	To	Size	Put in	Pulled out
		0	338	8 5/8		
		0	3799	5 1/2		2338

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Fill With sand to 3510 dump 5' sxs. cement

Plug top with 3 Hulls & 15 gel & 50 sxs. cement then 10 gel & 1hulls then wooden plug & 100 sxs. cement 60/40 pozmix 2% gel & 3% C.C. cement was used S.I.P. 300#  
Halliburton did Job.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Nicholas Casing Pulling License No. 6698

Address Box 108 Geneseo, Kansas 67144

STATE OF Ks COUNTY OF Rice, ss.

Allen D. Nicholas (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Allen D. Nicholas

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 4 day of Jan, 1985

Steven K. Prickett  
Notary Public

My Commission expires: \_\_\_\_\_



DRILLER'S WELL LOG

DATE COMMENCED: 6-22-80  
DATE COMPLETED: 6-28-80

Frank Black  
Strobel #1  
NW NE NW Sec. 23-21-14  
Stafford County, KS

ELEVATION: K.B.

FORMATION DATA

833	Anhydrite
3405-3681'	Lime
3681-3724'	Chert
3724-3792'	Sand
3792-3800'	Dolomite
3800'	RTD

Anhydrite	
Lansing	3405'
Viola	3681'
Simpson	3724'
Arbuckle	3792'
RTD	3800'

SURFACE PIPE:

Set @ 338' 8 5/8" 28#  
used casing w/325 sks  
50/50 Pozmix 2% Gel 3% c.c.

PRODUCTION PIPE:

Ran 122 jts 5 1/2" casing  
Set @ 3799' w/125 sks  
50/50 Pozmix salt saturated  
PD 3:15 p.m. 6-28-80

RECEIVED  
STATE CORPORATION COMMISSION

A F F I D A V I T

DEC 07 1984

STATE OF KANSAS }  
COUNTY OF BARTON } ss.


CONSERVATION DIVISION  
Wichita, Kansas

Joe Gerritzen, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Joe Gerritzen

Subscribed and sworn to before me this 17th day of July 1980.

Ulanda Richards  
Notary Public



My commission Expires:12-10-83