

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Stafford County, Sec. 23, Twp. 21S Rge. (E) 14 (W)

Location as "NE/CNW/SW" or footage from lines C NW SE NW

Lease Owner Burch Exploration, Ltd.

Lease Name STROBEL Well No. 1

Office Address 1011 Union Center, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 27 1964

Application for plugging filed October 27 1964

Application for plugging approved October 27 1964

Plugging commenced October 27 1964

Plugging completed October 27 1964

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Verbally - yes

Name of Conservation Agent who supervised plugging of this well Archie Elving of Pratt

Producing formation Depth to top Bottom Total Depth of Well 3840 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	265	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug at 250' w/ 1/4 sk hulls & 25 sx cement  
2nd plug at 40' w/ 1/2 sk hulls & 10 sx cement

RECEIVED  
STATE CORPORATION COMMISSION

OCT 29 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Abercrombie Drilling, Inc.  
Address 801 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. B. Lynn Herrington

(employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) B. Lynn Herrington  
801 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of October, 1964

My commission expires June 16, 1967 Leah Faye Hefke Notary Public.

CONTRACTOR'S WELL LOG

COMPANY: Burch Exploration, Ltd.  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 FARM: STROBEL #1  
 LOCATION: C NW SE NW  
 Section 23-21S-14W  
 Stafford County, Kansas  
 COMMENCED: October 20, 1964  
 COMPLETED: October 27, 1964

0	190	Sand
190	275	Shale
275	366	Sand
366	1590	Shale and Shells
1590	2290	Lime and Shale
2290	2500	Shale w/ Lime Str.
2500	3194	Lime and Shale
3194	3256	Lime
3256	3504	Lime and Shale
3504	3770	Lime
3770	3833	Lime and Shale
	3840	RTD

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 OCT 29 1964  
 CONSERVATION DIVISION  
 Wichita, Kansas

Set 8-5/8" Surface Casing at 265' with 225 sacks Sunset, 2% Gel.

DRY & ABANDONED

ELEVATION: 1938' D.F. & K.B.

TOPS:

Heebner	3289'	(-1351)
Toronto	3313'	(-1375)
Br. Lime	3409'	(-1471)
Lansing	3421'	(-1483)
B. K. C.	3640'	(-1702)
Conglom.	3692'	(-1754)

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I, B. Lynn Herrington, do hereby certify that the above and foregoing is a true and correct copy of the log of the STROBEL #1, C NW SE NW, Sec. 23-21S-14W, Stafford County, Kansas, as reflected by the files of Abercrombie Drilling, Inc.

*B. Lynn Herrington*  
 B. Lynn Herrington

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 28th day of October, 1964.

*Leah Faye Hefke*  
 Leah Faye Hefke, Notary Public

My commission expires June 16, 1967.