


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 31 Twp. 21 Rge. (E) (W)

Location as "NE/CNW/SW4" or footage from lines. NE NW SW
Lease Owner: Aylward Drilling Company
Lease Name: Russell Well No. 1
Office Address: 813 1st Natl. Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 11 19 59
Application for plugging filed April 11 19 59
Application for plugging approved April 11 19 59
Plugging commenced April 11 19 59
Plugging completed April 11 19 59
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot, St. John, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3883 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	265'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from total depth to 240'; set plug at 240' with 1/3 sack of hulls and 20 sacks of cement to 190'; heavy mud from 190' to 30'; plug at 30' with 1/3 sack of hulls and 10 sacks of cement to top of surface.

RECEIVED
STATE CORPORATION COMMISSION
MAY 21 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this report)
Name of Plugging Contractor: Aylward Drilling Company
Address: 813 1st Natl. Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Paul W. Hesse (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul W. Hesse
813 1st Natl. Bank Bldg. - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of April, 19 59

My commission expires December 11, 1961

Duane Jessup
DUANE JESSUP Notary Public.

PLUGGING
FILE SEC. 31 T. 21 R. 14
BOOK PAGE 22 LINE 22

RUSSELL NO. 1

Casing Record:
8 5/8" - 265'

Company: Aylward Drilling Company
Contractor: Aylward Drilling Company

Location: NE NW SW 31-21-14W
Stafford County
Kansas

Commenced: April 2, 1959
Completed: April 11, 1959

Elevation: 1959 R.B.

	<u>From</u>	<u>To</u>	<u>Remarks</u>	
Sand	0	215	Set 8 5/8" surface pipe @ 265' w/200 sacks cement.	
Shale	215	235		
Sand	235	245	Geological Tops:	
Shale	245	265		
Red bed & shale	265	345		
Sand	345	736		Heebner 3326
Sandy shale & red bed	736	867		Toronto 3335
Red bed & shale	867	960		Douglas 3355
Shale & shells	960	1650		Brown Lime 3447
Lime & shale	1650	1690		Lansing 3457
Lime, shale & shells	1790	1735		B/Kan. City 3680
Lime & shale	1735	1835		Viola 3754
Lime w/shale	1835	1945	Simpson 3804	
Lime & shale	1945	2120	Arbuckle 3858	
Shale & sandy lime	2120	2265	R.T.D. 3883	
Shale & lime	2265	2370	No drill stem test.	
Shale & Shells	2370	2550		
Lime & shale	2550	2720		
Shale, lime streaks	2720	2760		
Shale & lime	2760	2866		
Shale w/lime	2866	3080		
Shale & Lime	3080	3110		
Lime	3110	3300		
Lime & Shale	3300	3348		
Chalky lime & shale	3348	3425		
Shale	3425	3457		
Lime	3457	3505		
Lime & shale	3505	3570		
Lime	3570	3675		
Lime & shale	3675	3718		
Cherty lime	3718	3788		
Lime & chert	3788	3800		
Shale & lime	3800	3883 T.D.	D & A	

RECEIVED
STATE COMPLETION COMMISSION
MAY 21 1959
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul Whesse

Subscribed and sworn to before me this 21st day of April, 1959.

Duane Jessup
DUANE JESSUP Notary Public

My commission expires December 11, 1961

PLUGGING
FILE SEC 31 T. 21 R. 14
BOOK PAGE 29 LINE 29