


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 31 Twp. 21 Rge. 14 (E) W(W)
Location as "NE/CNW/SW" or footage from lines NE NW SE
Lease Owner Franco Central Oil Company
Lease Name Russell Well No. 1
Office Address Fourth National Bank Building, Wichita
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed July 28 19 54
Application for plugging filed July 30 19 54
Application for plugging approved July 28 19 54
Plugging commenced 1 P.M., July 28 19 54
Plugging completed 3:30 P.M., July 28 19 54
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation No Depth to top - Bottom - Total Depth of Well - Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4	230	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with heavy Rotary mud to top. Introduced regular cement plug into 10 3/4 surface casing. Squeezed 100 sacks of cement by Globe Cementing Co., Stopped plug at 220' cement to bottom of cellar

RECEIVED
STATE CORPORATION COMMISSION
AUG 4 1954
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Globe Cementing Co.
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. M. Clothier (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. M. Clothier
512 Fourth National Bank Bldg., Wichita, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of July, 19 54

My commission expires Oct. 21, 1957 Rebecca Hill Notary Public.

PLUGGING
FILE SEC 31 T 21 R 14W
PAGE 52 LINE 12

RECEIVED
STATE CORPORATION COMMISSION
AUG 4 1954
CONSERVATION DIVISION
Wichita, Kansas

THE CARL TODD DRILLING COMPANY

404 KFH Building
Wichita 2, Kansas

FRANCO CENTRAL OIL COMPANY

#1 Russell
NE NW SE 31-21-14W
Stafford County, Kansas

COMMENCED: July 16, 1954
COMPLETED: July 28, 1954

Surface Casing: 10 3/4" O.D.
32# casing set at 230' cemented
with 175 sacks

ELEVATION: 1957 R.B.

			<u>Tops</u>
0	230	Sand, shale	
230	255	Shale, shells	Heebner 3320
255	270	Iron, shale	Brown Lime 3436
270	330	Shale, red bed	Lansing 3445
330	430	Sand	Base Kansas City 3677
430	575	Shale, red bed, shells	Marm. 3698
575	880	Red bed, shale	Viola 3748
880	905	Anhydrite	Simpson 3787
905	1460	Shale, shells	Arbuckle 3851
1460	1680	Shale, shells, salt	
1680	2095	Shale, lime	
2095	2260	Shale	
2260	2375	Lime, shale	
2375	2770	Shale	
2770	3035	Shale, lime	
3035	3105	Lime	
3105	3140	Shale, lime	
3140	3345	Lime	
3345	3436	Shale, lime	
3436	3793	Lime	
3793	3800	Lime, chert	
3800	3835	Lime, sand	
3835	3865	Lime and arbuckle	
3865	3881	Lime	
3881		Rotary Total Depth	

I hereby certify that the above is a true and correct log to the best of my knowledge and belief.

THE CARL TODD DRILLING COMPANY

Carl Todd

PLUGGING
WELL SEC 31 T 21 R 14 W
BOOK PAGE 52 LINE 12

RECEIVED
STATE CORPORATION COMMISSION
AUG 1 1954
CONSERVATION DIVISION
Wichita, Kansas