

R

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Stafford County. Sec 31 Twp. 21S Rge. (E) 14 (W)

Location as "NE/CNW/SW" or footage from lines NE SE NE

Lease Owner Rains & Williamson Oil Co., Inc.

Lease Name LOVE Well No. 1

Office Address 1425 Wichita Plaza - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-21 19 67

Application for plugging filed 8-21 19 67

Application for plugging approved 8-21 19 67


Plugging commenced 8-21 19 67

Plugging completed 12:00 midnight 8-21 19 67

Reason for abandonment of well or producing formation No oil or gas found  
in commercial quantities.

If a producing well is abandoned, date of last production -- 19 --

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above  
Section Plot

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas

Producing formation None Depth to top -- Bottom -- Total Depth of Well 3860 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	288.80'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Spotted 100 sacks 50-50 pozmix with 6% gel at 540'. Mud back to 40', set solid bridge and capped with 10 sacks, 2 sacks in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 30 1967

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.

Address 1425 Wichita Plaza - Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Wilson Rains (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains Wilson Rains

1425 Wichita Plaza - Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 29 day of August, 19 67

Sherry Gish  
Sherry Gish Notary Public.

My commission expires June 30, 1971

67

ROTARY DRILLING LOG

Operator: Rains & Williamson  
 Oil Co., Inc.  
 LOVE #1  
 NE SE NE Sec. 31-21S-14W  
 Stafford County, Kansas

Contractor: Rains & Williamson  
 Oil Co., Inc.  
 Commenced: 8-13-67  
 Completed: 8-21-67

Remarks: Set 8-5/8" surface casing at 288.80' w/ 275 sacks GL-3 cement.

Formations

Sand	240'
Clay	288'
Shale	330'
Sand	425'
Shale	799'
Anhydrite	817'
Shale	1700'
Lime and Shale	2228'
Shale and Lime	2505'
Shale	2765'
Shale and Lime	3225'
Lime and Shale	3445'
Lime	3786'
Lime and Chert	3815'
Lime	3860'
Rotary Total Depth (D & A)	3860'

RECEIVED  
 STATE CORPORATION COMMISSION

AUG 30 1967


CONSERVATION DIVISION  
 Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.

  
 \_\_\_\_\_  
 Wilson Rains

Subscribed and sworn to before me, a Notary Public within and for the State of Kansas, County of Sedgwick, this 29th day of August, 1967.

  
 \_\_\_\_\_  
 Sherry Gish Notary Public

My Commission Expires:  
 June 30, 1971