

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

STAFFORD County. Sec. 28 Twp. 21S Rge. 11 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE, SE, NE

Lease Owner RAYMOND OIL COMPANY

Lease Name HEIM Well No. 1

Office Address 410 - 4th NATL. BANK BLDG. WICHITA, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed JULY 15, 19 60

Application for plugging filed JULY 16, 19 60

Application for plugging approved JULY 16, 19 60


Plugging commenced JULY 16, 19 60

Plugging completed JULY 16, 19 60

Reason for abandonment of well or producing formation No productible zone.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well FRANK BROADFOOT

Producing formation Depth to top Bottom Total Depth of Well 3489' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	237'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Gunned up pits forming heavy mud, filled hole up to 210' w/heavy mud, pushed wooden plug and 1/4 sx. hulls to 210', capped with 20 sx. cement through drill pipe.
Filled hole up to 35' w/heavy mud, pushed wooden plug and 1/4 sx. hulls to 35', filled hole up to base of well cellar with 10 sx. cement.

RECEIVED
STATE CORPORATION COMMISSION
AUG 16 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GARVEY DRILLING COMPANY
Address ROUTE #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
VERNE A. MORRIS (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Verne A. Morris
ROUTE #2, GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 21st day of July, 19 60

Notary Public

My commission expires November 12, 1962

Raymond-Champlin #1 HEIM
 SE SE NE, 28-21S-11W
 Stafford County, Kansas

Elevation: 1742 KB
 1741 DF
 1738 GL

Contractor: Garvey Drilling Company-Rig #3
 Commenced: July 6, 1960
 Completed: July 16, 1960

Casing Record:
 8-5/8" @ 237' w/250 sacks

Figures Indicate Bottom of Formation

<u>Formation</u>	<u>Depth</u>
Surface sand	150
Red Bed & Shells	237
Red Bed	450
Anhydrite	475
Shale, Shells, & Anhydrite	1035
Shale	1340
Lime	1995
Lime & Shale	2375
Lime	2623
Shaly Lime	2745
Lime	2949
Shale	2954
Lime & Shale	2968
Lime	2981
Shale	3083
Lime	3090
Shale	3102
Lime	3361
Chert	3389
Shale	3392
Sand	3406
Shale	3439
Dolomite	3489

Tops:

Anhydrite (driller's)	450
Tarkio	2409
Topeka	2657
Heebner	2950
Toronto	2968
Brown Lime	3083
Lansing	3102
Conglomerate	3361
Simpson shale	3389
Simpson sand	3392
Arbuckle	3439
RTD	3489
D & A	

RECEIVED
 STATE CORPORATION COMMISSION

AUG 16 1960

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I hereby certify that the above is true and correct to the best of my knowledge.

Wm. M. Raymond
 Wm. M. Raymond
 President

Subscribed and sworn to before me this 22nd day of July, 1960.

Bernice Boldt
 Bernice Boldt
 Notary Public