


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 28 Twp. 21S Rge. (E) 11 (W)
Location as "NE/CNW/SW" or footage from lines SE-NW-NE
Lease Owner Aspen Drilling Co.
Lease Name Wolf 'A' Well No. 7
Office Address P.O. Box 783, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 28 19 70
Application for plugging filed May 1 19 70
Application for plugging approved 19
Plugging commenced April 28 19 70
Plugging completed same 19
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstien
Producing formation Depth to top Bottom Total Depth of Well 3450 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 240', wood plug, 1/2 sack hulls and 30 sacks cement through drill pipe;
mud to 40', wood plug, 1/2 sack hulls and 10 sacks cement.
2 sacks cement in rathole.

RECEIVED
STATE CORPORATION COMMISSION
MAY 4 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Aspen Drilling Co.
Address P. O. Box 783, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
William S. Schachle (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William S. Schachle
P.O. Box 783, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of May, 1970

My commission expires April 18, 1972
Theora Holleman Notary Public.

DRILLERS LOG

COMPANY: Aspen Drilling Co.
 CONTRACTOR: Aspen Drilling Co.
 LEASE NAME: Wolf 'A' #7
 LOCATION: SE-NW-NE Sec. 28-21S-11W
 Stafford County, Kansas
 ELEVATION: 1743' K. B.
 SURFACE CASING: 6 jts. (242') 8 5/8"
 COMMENCED: April 21, 1970
 COMPLETED: April 28, 1970
 ROTARY TOTAL DEPTH: 3450'

<u>FORMATION</u>	<u>DEPTH</u>
Sand	60
Shale	150
Sand	190
Red Bed	462
Anhydrite	490
Shale	985
Shale & Shells	1325
Shale & Lime	2557
Lime & Shale	3245
Lime	3379
Sand & Shale	3400
Lime	3450

Ran 6 jts. (242') 8 5/8" casing set at 247' with 200 sacks cement. Cement circulated.

DST #1 3359-3379
 DST #2 3380-3400

LOG TOPS

Anhydrite	463
Heebner	2944
Toronto	2962
Douglas	2976
Brown Lime	3077
Lansing	3097
Base K. C.	3343
Viola Chert	3352
Simpson Sand	3369
Arbuckle	3412

AFFIDAVIT

State of Kansas)
) ss:
 County of Barton)

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.

William S. Schachle
 William S. Schachle, Affiant

Subscribed and sworn to before me this 1st day of May, 1970.

Theora Holleman
 Theora Holleman, Notary Public

My commission expires: April 18, 1972

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 4 1970
 CONSERVATION DIVISION
 Wichita, Kansas