

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 28 Twp. 21S Rge. (E) 11(W)

Location as "NE/CNW%SW%" or footage from lines C SL NW SE
Lease Owner Aspen Drilling Co.
Lease Name Wolf 'A' Well No. 6
Office Address P. O. Box 783, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 30 19 68
Application for plugging filed Sept. 5 19 68
Application for plugging approved 19
Plugging commenced August 31 19 68
Plugging completed same 19
Reason for abandonment of well or producing formation dry hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ralph J. Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 240', wood plug and 25 sacks cement,
Mud to 40', wood plug, 1/2 sack hulls and 10 sacks cement.


RECEIVED
STATE CORPORATION COMMISSION
SEP 9 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Company tools
Address see above

STATE OF Kansas, COUNTY OF Barton, ss.
William S. Schachle (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William S. Schachle
William S. Schachle
P. O. Box 783, Great Bend, Kansas
(Address)



Subscribed and sworn to before me this 5th day of September, 1968

Theora Holleman
Notary Public.

My commission expires April 18, 1972

DRILLERS LOG

COMPANY: Aspen Drilling Co.
 CONTRACTOR: Aspen Drilling Co.
 LEASE NAME: Wolf 'A' #6
 LOCATION: C SL NW SE Sec. 28-T21S-R11W
 Stafford County, Kansas
 1745 KB
 ELEVATION: 1745 KB
 SURFACE CASING: 6 jts. (242') 8 5/8"
 COMMENCED: August 24, 1968
 COMPLETED: August 31, 1968
 ROTARY TOTAL DEPTH: 3450'

<u>FORMATION</u>	<u>DEPTH</u>	
Sand & Shale	110	Ran 6 jts. (242') 8 5/8" csg.
Red Bed	464	Set at 250', cemented with
Anhydrite	497	250 sacks. Cement circulated.
Shale	660	
Shale-Shells	1380	DST #1 3113-3150
Shale-Lime	1725	DST #2 3223-3247
Lime-Shale	2135	DST #3 3380-3402
Shale-Lime	2820	
Lime	3053	Ran electric log.
Lime-Shale	3150	
Lime	3402	D & A
Lime-Chert	3405	
Lime	3450	
RTD	3450	

LOG TOPS

Anhydrite	462
Heebner	2942
Toronto	2960
Douglas	2974
Brown Lime	3076
Lansing	3100
Base K.C.	3350
Viola Chert	3365
Simpson S.S.	3387
Base Simp. S.S.	3403
Arbuckle	3432
Log TD	3452

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 27 1968
 CONSERVATION DIVISION
 Wichita, Kansas

AFFIDAVIT

State of Kansas)
) ss
 County of Barton)

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.

William S. Schachle
 William S. Schachle

Subscribed and sworn to before me this 10th day of September, 1968.

Theora Holleman
 Theora Holleman, Notary Public



My Commission expires April 18, 1972.