

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:

Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

*Reid
2-17-72*



Locate well correctly on above
Section Plat

Stafford County, Sec. 28 Twp. 21 Rge. 11 (E) 11 (W)
Location as "NE/CNWESW" or footage from lines. SE NE SW
Lease Owner Aspen Drilling Company
Lease Name Heim Well No. 1
Office Address Box 783, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 19__
Application for plugging filed 19__
Application for plugging approved 19__
Plugging commenced March 3 19 72
Plugging completed March 7 19 72
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation Depth to top Bottom Total Depth of Well 3450 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	248'	8 5/8"	248'	none
		0	3420'	4 1/2"	3420'	2467.61

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded back to 3100' and dumped 4 sacks of cement.
Plugged well with 2 sacks of hulls, 15 sacks of mud and 100 sacks of cement.

Name of Plugging Contractor PIPE PULLERS, INC. (If additional description is necessary, use BACK of this sheet)
Address Box 486, Ellinwood, Kansas 67526

STATE OF KANSAS COUNTY OF BARTON ss.
Evelyn Roth (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of March, 19 72

My commission expires Feb. 10, 1975 George A Meyer Notary Public.

DRILLERS LOG

COMPANY: Aspen Drilling Co.
 CONTRACTOR: Aspen Drilling Co.
 LEASE NAME: Heim #1
 LOCATION: SE NE SW, Sec.28-T21S-R11W
 Stafford County, Kansas
 1746 KB
 ELEVATION: 6 jts.(243') 8 5/8"
 SURFACE CASING: 102 jts.(3439') 4 1/2"
 OIL STRING: 7-1-68
 COMMENCED: 7-9-68
 COMPLETED: 3450'
 ROTARY TOTAL DEPTH: 3450'

<u>FORMATION</u>	<u>DEPTH</u>
Red Bed	249
Shale	458
Anhydrite	476
Shale	1525
Shale-Lime	1710
Lime-Shale	2287
Shale-Lime	2515
Lime-Shale	3073
Lime	3320
Lime-Chert-Sand	3390
Lime-Sand	3400
Lime-Shale	3428
Arbuckle	3450

Ran 6 jts.(243') 8 5/8" set at 248', cemented with 250 sacks. Cement circulated.
 DST #1 2968-3073
 DST #2 3122-3142
 DST #3 3145-3175
 DST #4 3211-3241
 DST #5 3340-3390

Ran electric log.

Ran 102 jts.(3439') 4 1/2" set at 3420', cemented with 125 sacks.

LOG TOPS

Anhydrite	458
Howard	2549
Topeka	2662
Heebner	2937
Toronto	2956
Douglas	2969
Brown Lime	3068
Lansing	3091
Base K.C.	3342
Viola	3352
Simpson Sand	3375
Base Simpson Sand	3394
Arbuckle	3426
Log TD	3449

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 17 1972
 CONSERVATION DIVISION
 Wichita, Kansas

AFFIDAVIT


State of Kansas)
) ss:
 County of Barton)

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.

William S. Schachle
 William S. Schachle

and sworn to before me this 12th day of July, 1968.

Theora Holleman
 Theora Holleman, Notary Public



Commission expires: 4-18-72