


15-009-00211-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS. 67202



Locate well correctly on above
Section Plat

Barton County. Sec. 20 Twp. 16 Rge. 12 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE SW SE
Lease Owner John J. Darrah
Lease Name Christians #1 Well No.
Office Address Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 3/26/79 19
Plugging completed 3/30/79 19
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Rankin
Producing formation Depth to top Bottom Total Depth of Well 3394
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	200	none
				5 1/2"	3374'	2618'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Sanded to 3110' and set 5 sacks cement. Shot pipe at 2714', 2615', pulled 81 joints.
Pumped 6 sacks hulls, 25 sacks gel, 125 sacks pos, 4% gel.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature)

CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of April, 19 79



MARGARET MELCHER
Statewide
My Appt. Exp. Feb. 15, 1983

Margaret Melcher
Notary Public.

My commission expires

RECEIVED
STATE CORPORATION COMMISSION

APR 10 1979

CONSERVATION DIVISION
Wichita, Kansas

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-009-00211-00-00

Company- FRANCO CENTRAL OIL CO.
 Farm- Christians' No. 1

SEC. 20 T. 16 R. 12W
 SE SW SE

Total Depth. 3394

Comm. 5-5-53

Comp. 5-15-53


Shot or Treated.

Contractor. Glenn R. Nye Drlg. Co.

Issued. 7-11-53

County Barton

KANSAS



8 5/8" 373'
 5 1/2" 3374'

CASING:

Elevation. 1923 R.B.

Production. Pmp. 35 bbls. &
 no wtr.

Figures indicate Bottom of Formations.

surface soil & clay	50
clay & sand	30
shale & sand	180
sand gry & shale	205
shale gry & sand	310
surface shale & gumbo	373
shale	398
sand & shale	455
shale & gumbo	530
red bed & shale	837
anhyd.	865
shale & shells	1360
shale	1670
lime & shale	2740
lime	2865
lime & shale	3120
lime	3215
lime & shale	3250
lime	3355
lime & congl.	3375
lime & congl.	3394
Total Depth	

RTD

Tops:	
Howard	2702
Topoka	2778
Heebner	3020
Toronto	3037
Douglas	3048
Lansing	3121
Congl.	3359
Arbuckle	3373

All meas. from top of rotary bushing

RECEIVED
 STATE CORPORATION COMMISSION

MAR 29 1979

CONSERVATION DIVISION
 Wichita, Kansas