

WELL PLUGGING RECORD

Locate well correctly on above
Section Plat

Barton County, Sec. 20 Twp. 16S Rge. (E) 12 (W)
Location as "NE/CNW%SW%" or footage from lines W/2 SE/4 SE/4
Lease Owner John Jay Darrah
Lease Name Beaver Townsite Well No. 2
Office Address 303 South Main Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed May 31 19 57
Application for plugging filed May 31 19 57
Application for plugging approved May 31 19 57
Plugging commenced May 31 19 57
Plugging completed May 31 19 57
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production. --- 19---
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage
Producing formation -- Depth to top -- Bottom -- Total Depth of Well 3425 Feet
Show depth and thickness of all water, oil and gas formations.

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from 3425 feet to 330 feet. Set plug at 330 feet. Dumped 1/2 sack hulls and 20 sacks cement on plug and completed filling hole with heavy mud to 35 feet. Set second plug at 35 feet. Dumped 1/2 sack hulls and 10 sacks cement on plug to fill to bottom of cellar.

STATE CORPORATIONS

JUN 5 1971

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnett Drilling, Inc.

Address 409 First National Bank Building, Wichita 2, Kansas

Wichita, Kansas

CONSERVATION DIVISION

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Louise Burnett ^{Contractor} (employee of ~~owner~~ or ~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Louise Burness
409 First National Bank Building, Wichita 2, Ks.
 (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of June, 1957

My commission expires February 27, 1960

Notary Public.



PLUGGING
FILE SEP 20 T. 16 R. 12W
BOOK PAGE 17 LINE 13

15-009-05943-00-00

BARNETT DRILLING, INC.
LOG OF BEAVER TOWNSITE NO. 2
C W/2 SE/4 SE/4 OF SECTION 20-169-12W
BARTON COUNTY, KANSAS.

Commenced: 5-21-'57

Completed: 5-31-'57

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Shale	-0-	205	Set 8-5/8" Casing at 418 feet; cemented with 190 sacks.
Sand	205	230	
Shale and Shells	230	414	
Shale	414	465	
Shale and Shells	465	1660	
Lime and Shale	1660	1885	
Lime	1885	1965	
Lime and Shale	1965	2690	
Lime	2690	2990	
Lime and Shale	2990	3090	
Lime	3090	3425	
Total Depth		3425	Dry and Abandoned

CERTIFICATE

I, Louise Burnett, of Barnett Drilling, Inc. certify to the best of my knowledge and belief, that the foregoing is a true and correct log of Beaver Townsite Well No. 2, located in the approximate center of the W/2 SE/4 SE/4 of Section 20-169-12W, Barton County, Kansas.

Louise Burnett

Subscribed and sworn to by and before me in and for the County of Sedgwick, State of Kansas this 4th day of June, 1957.

Michael F. Willis

My commission expires February 27, 1960.

RECEIVED
 JUN 14 1957
 DIVISION
 Kansas

PLUGGING			
FILE	SEC 20	T 16	R 12W
BOOK	PAGE 17	LINE	13