

15-009-19116-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

## WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Barton SEC. 20 TWP. 16 RGE. 12W E/W  
Location as in quarters or footage from lines:

E/2 E/2 SE/4

|  |  |  |  |
|--|--|--|--|
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |

Lease Owner Palomino Petroleum (John Jay Barnack, Jr.)

Lease Name Beaver Township Townsite Well No. 43

Office Address Box 18610 Wichita, Kansas 67218

Character of Well (Completed as Oil, Gas or Dry Hole):

Date Well Completed

Application for plugging filed

Plugging commenced 9-23-81

Plugging completed 9-30-81

Reason for abandonment of well or producing formation

Depleted

Was permission obtained from the Conservation Division or it's

Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz

Producing formation Depth to top bottom T.D. 3355'

Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## Casing Record

| Formation | Content | From | To | Size   | Put in | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 5-1/2" | 3354'  | 1721'      |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed; from feet to feet for each plug set.

Moved in on location, plugged off bottom with sand to 3300' and set 7 sacks cement, got 16" stretch, shot casing @2395', 2269', 2140', 2020', 1890', 1790' and 1692'. Pulled 53 Joints of casing. Plugged well with 5 sacks hulls, 20 sacks gel, 2 sacks hull 150 sacks 50/50 pos, 2% gel, 3% ee. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso

Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of October, 19 81

My Commission expires:



Irene Hoover  
Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 29 1981

CONSERVATION DIVISION  
Wichita, Kansas

## WELL LOG

15-009-19116-00-00

Date Started: May 23, 1959  
 Date Completed: June 3, 1959

Beaver Townsite #3  
 E/2 E/2 SE/4  
 Section 20-16-12W  
 Barton County, Kansas

|            |       |       |
|------------|-------|-------|
| Elevation  | 1925' | K.B.  |
| Anhydrite  | 819'  | -1106 |
| Heebner    | 2995' | -1070 |
| Brown Lime | 3080' | -1155 |
| Lansing    | 3095' | -1170 |
| Arbuckle   | 3352' | -1427 |
| R.T.D.     | 3355' | -1430 |

5 1/2" set at 3354' with  
 125 sacks Pozmix

|       |         |                   |
|-------|---------|-------------------|
| 0'    | - 40'   | Surface Clay      |
| 40'   | - 48'   | Sand              |
| 48'   | - 125'  | Clay Shells       |
| 125'  | - 130'  | Sand              |
| 130'  | - 220'  | Shale and Shells  |
| 220'  | - 225'  | Sand              |
| 225'  | - 260'  | Shale and Shells  |
| 260'  | - 265'  | Sand              |
| 265'  | - 361'  | Shale and Shells  |
| 361'  | - 375'  | Shale and Red Bed |
| 375'  | - 495'  | Shale and Clay    |
| 495'  | - 819'  | Red Bed           |
| 819'  | - 850'  | Anhydrite         |
| 850'  | - 1240' | Shale and Shells  |
| 1240' | - 1460' | Salt Shale        |
| 1460' | - 1540' | Shale Lime        |
| 1540' | - 1935' | Lime and Shale    |
| 1935' | - 2255' | Lime and Shale    |
| 2255' | - 2615' | Lime and Shale    |
| 2615' | - 2720' | Lime and Shale    |
| 2720' | - 2840' | Lime              |
| 2840' | - 2995' | Lime              |
| 2995' | - 3090' | Heebner           |
| 3090' | - 3095' | Lime              |
| 3095' | - 3208' | Lansing           |
| 3208' | - 3280' | Lime              |
| 3280' | - 3352' | Lime              |
| 3352' | - 3355' | Arbuckle          |
| 3355' |         | R.T.D.            |

RECEIVED  
 STATE CORPORATION COMMISSION  
 AUG 24 1961  
 CONSERVATION DIVISION  
 Wichita, Kansas

## AFFIDAVIT

State of Kansas . . . . . County of Barton

I, Cecil M. Olson, employee of the owner, do swear that the  
 statements and matter herein contained are true to the best of my knowledge.

THE DUKE DRILLING COMPANY

BY: C. Olson

Subscribed and sworn before me this 3rd day of July, 1959.

Paul E. Stenison  
 NOTARY PUBLIC

My commission expires: June 24, 1963.