

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185-20261-0000

LEASE NAME SMITH ESTATE

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

3630 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 29 TWP. 21S RGE. 11 ~~W~~ or (W)

COUNTY Stafford

Date Well Completed 4-18-70

Plugging Commenced 10-20-86

Plugging Completed 10-20-86

LEASE OPERATOR Leben Oil Corporation

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE# (918) 494-0000 OPERATORS' LICENSE NO. 6566

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well).

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 1, Dodge City

Is ACO-1 filed? on old form if not, is well log attached? ----

Producing Formation LKC, Conglomerate Depth to Top 3256 Bottom 3400 T.D. 3480

Simpson

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC	Oil	3256	3348	8-5/8	226	-0-
Conglomerate	Oil	3366	86	5-1/2	3479	-0-
Simpson	Oil	3396	3400			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Pumped 25 SXS cmt., 3 hulls, 20 SXS gel from TD to 2301'. Pumped 100 SXS cmt. from 1117'-SURF. Pumped 85 SXS cmt. down annulus.

JOB COMPLETE

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468, Tulsa, OK 74121-1468

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filled that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg

(Address) P.O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 28th day of October, 19 86

Oct 30 1986

Carol Sue Brungardt  
Notary Public

My Commission Expires: 2/11/89

10-30-86

DRILLERS LOG

COMPANY: Leben Drilling, Inc.  
 CONTRACTOR: Aspen Drilling Co.  
 LEASE NAME: Smith Estate #1  
 LOCATION: N/2 S/2 NE/4 Sec. 29-21S-11W  
 Stafford County, Kansas  
 1747 K. B.  
 ELEVATION: 6 jts. (222') 8 5/8"  
 SURFACE CASING: 111 jts. (3500') 5 1/2"  
 OIL STRING: April 9, 1970  
 COMMENCED: April 18, 1970  
 COMPLETED: 3480'.  
 ROTARY TOTAL DEPTH:

<u>FORMATION</u>	<u>DEPTH</u>
Sand	70
Shale	190
Red Bed	227
Shale & Red Bed	500
Shale	1075
Shale & Lime	2655
Lime & Shale	2910
Lime	3100
Lime & Shale	3216
Lime	3380
Conglomerate	3443
Arbuckle	3461
Lime	3480

Ran 6 jts. (222') 8 5/8" casing set at 226' w/225 sacks cement. Cement circulated.

- DST #1 3077-3100'
- DST #2 3194-3216'
- DST #3 3252-3291'
- DST #4 3361-3413'
- DST #5 3390-3418'

Ran Electric Log.

Ran 111 jts. (3500') 5 1/2" casing set at 3479' w/125 sacks 50/50 Pozmix.

AFFIDAVIT

State of Kansas )  
 ) SS:  
 County of Barton )

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.

*William S. Schachle*  
 William S. Schachle, Affiant

Subscribed and sworn to before me this 21st day of April, 1970.

*Theora Holleman*  
 Theora Holleman, Notary Public

My commission expires: April 18, 1972.

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 CONS. DIV. WICHITA, KS

OCT

21  
22 B