

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-20271-0000

LEASE NAME SMITH ESTATE

WELL NUMBER 2

2970 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 29 TWP. 21S RGE. 11 XR or (W)

COUNTY Stafford

Date Well Completed 6-1-70

Plugging Commenced 10-20-86

Plugging Completed 10-20-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Leben Oil Corporation

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE#(918) 494-0000 OPERATORS' LICENSE NO. 6566

Character of Well Oil/SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well).

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 1, Dodge City

Is ACO-1 filed? on old form if not, is well log attached? ---

Producing Formation LKC Depth to Top 3296 Bottom 3314 T.D. 3653

Arbuckle 3550 3611

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
LKC	Oil	3296	3314	8-5/8	226	-0-
Arbuckle	Water	3550	3611	5-1/2	3550	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Pumped 25 SXS cmt., 3 hulls, 20 SXS gel from TD to 2474'. Pumped 100 SXS cmt. from 1117-SURF. Pumped 100 SXS cmt. down annulus.

JOB COMPLETE

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468, Tulsa, OK 74121-1468

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first, duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct; so help me God.

(Signature) C. Van Valkenburg

(Address) P.O. Box 21468, Tulsa, OK 74121-

1468

SUBSCRIBED AND SWORN TO before me this 28th day of October, 1986

Carol Sue Brungardt
Notary Public

My Commission Expires: 2/11/89

*Field
10-3089*

DRILLERS LOG


COMPANY: Leben Drilling, Inc.
 CONTRACTOR: Aspen Drilling Co.
 LEASE NAME: Smith Estate #2
 LOCATION: S/2-S/2-NE/4 Section 29
 T21S-R11W
 Stafford County, Kansas
 SURFACE CASING: 6 jts. (222') 8 5/8" casing
 OIL STRING: 116 jts. (3554') 5 1/2" casing
 COMMENCED: 5-23-70
 COMPLETED: 6-1-70
 ROTARY TOTAL DEPTH: 3611'

<u>FORMATION</u>	<u>DEPTH</u>	
Sand	110	Ran 6 jts. (222') 8 5/8" casing set
Red Bed & Shale	200	at 226' w/225 sacks cement.
Shale	228	Cement did circulate.
Shale & Red Bed	935	
Shale & Shells	1350	DST #1 3138-3202
Shale & Lime	2210	DST #2 3250-3278
Shale	2560	DST #3 3280-3295
Shale & Lime	2755	DST #4 3297-3375
Lime & Shale	3050	DST #5 3370-3414
Shale & Lime	3145	DST #6 3344-3440
Lime & Shale	3202	
Lime	3414	Ran electric log.
Chert	3440	
Conglomerate	3549	Ran 116(3554') 5 1/2" casing set
Arbuckle	3611	at 3550' w/150 sacks.


AFFIDAVIT

State of Kansas)
) ss:
 County of Barton)

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.


 William S. Schachle, Affiant

Subscribed and sworn to before me this 3rd day of June, 1970.


 Theora Holleman, Notary Public

My commission expires: April 18, 1972