


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec 32 Twp. 21S Rge. 11 (E) x (W)

Location as "NE/CNWxSW" or footage from lines _____
Lease Owner Raymond Oil Co., Inc.
Lease Name Wolf Well No. 1
Office Address 410 Fourth National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed August 22 1961
Application for plugging filed January 17 1967
Application for plugging approved January 18 1967
Plugging commenced January 23 1967
Plugging completed February 7 1967
Reason for abandonment of well or producing formation No longer commercially productive



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production December 29 1966
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Anchie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 253 | |
| | | | | 5 1/2" | 3549 | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled back in the 5 1/2" with gravel and dumped 5 sacks of cement. Shot pipe off at 2331.70'. Pulled pipe and squeezed hole with Halliburton; using 10 sacks of Jet-Mud and 80 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 13 1967
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Best Self
Address Hutchinson, Kans.

STATE OF Kans. COUNTY OF Reno, ss. Employee (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed, and that the same are true and correct. So help me God.

(Signature) Best Self
R. R. #4, Hutchinson, Kans.
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of February, 1967
October 18, 1969
My commission expires _____ Notary Public.



DRILLER'S LOG

COMPANY:
CONTRACTOR:
FARM:
LOCATION:

CONTINENTAL OIL CO.
LEBEN DRILLING, INC.
WOLF #1
2310' FROM SOUTH 1650' FROM EAST
SEC. 32-21S-11W STAFFORD CO., Ks.
8-9-61
8-22-61

COMMENCED:
COMPLETED:

| | | |
|------|------|-------------------------------|
| 0 | 40 | Sand & Shale |
| 40 | 195 | Shale & Shells |
| 195 | 500 | Shale |
| 500 | 530 | Anhydrite |
| 530 | 795 | Shale, Shells & Sand |
| 795 | 1445 | Shale & Shells |
| 1445 | 1660 | Lime & Shale |
| 1660 | 1800 | Lime |
| 1800 | 2040 | Lime & Shale |
| 2040 | 2275 | Shale |
| 2275 | 2445 | Shale & Lime |
| 2445 | 2700 | Shale |
| 2700 | 2810 | Shale & Lime |
| 2810 | 2930 | Lime & Shale |
| 2930 | 3025 | Lime |
| 3025 | 3125 | Shale & Lime |
| 3125 | 3210 | Lime & Shale |
| 3210 | 3416 | Lime |
| 3416 | 3435 | Chert |
| 3435 | 3452 | Chert & Lime |
| 3452 | 3496 | Lime |
| 3496 | 3506 | Arbuckle |
| 3506 | 3550 | Lime |
| | 3550 | Rotary Total Depth - Set Pipe |

RECEIVED
STATE CORPORATION COMMISSION

JAN 18 1967

CONSERVATION DIVISION
Wichita, Kansas

Set 8 5/8" casing @ 253 with 250 sz Common cement.

I, Byron Johnson, do hereby certify that the above and foregoing is a true and correct copy of the log of the Wolf #1, located 2310' from South and 1650' from East lines of Section 32, Township 21 South, Range 11 West, Stafford County, Kansas, as reflected by the files of Leben Drilling, Inc.

Byron Johnson
Byron Johnson

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 25th day of August, 1961.

Ulanda Nichols
Ulanda Nichols, Notary Public

Expires:

Pa. Catfish Society



1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 1
AUG 1961
KANSAS
DIVISION
PRODUCTION

Handwritten signature

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 1
AUG 1961
REC'D
LYONS DISTRICT
PRODUCTION

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 1