

WELL PLUGGING RECORD


Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 211 No. Broadway
 Wichita, Kansas

STAFFORD

County, Sec. 32 Twp. 21S Rge. 11W (E)____(W)

Location as "NE/CNW%SW%" or footage from lines C SE NE
 Lease Owner CONTINENTAL OIL COMPANY
 Lease Name BEST HUNTING CLUB Well No. 1
 Office Address BOX 2197, HOUSTON, TEXAS
 Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
 Date well completed SEPTEMBER 19, 1962
 Application for plugging filed SEPTEMBER 19, 1962
 Application for plugging approved SEPT. 19, 1962
 Plugging commenced SEPT. 20, 1962
 Plugging completed SEPT. 20, 1962
 Reason for abandonment of well or producing formation DRY HOLE

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well FRANK BROADBENT, 222 GO, MAIN, ST. JOHN, KANSAS
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3503 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>SAND, SURF. CLAY & REDED</u>	<u>SURF. CSG.</u>	<u>-0-</u>	<u>282'</u>	<u>8-5/8"</u>	<u>282'</u>	<u>NONE</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED: Filled hole with mud 3503' up to 240'. Bridged with 3 gal. hulls, Halliburton plug, 20 sx. cement through drill pipe by Halliburton. Filled hole with mud up to 35'. Bridged with 1/2 sk. hulls, Halliburton plug, 10 sx. cement through drill pipe by Halliburton to cellar -0-.

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 24 1962
 CONSERVATION DIVISION
 Wichita, Kansas

Job complete at 3 p.m. 9-20-62.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SIERRA PETROLEUM CO., INC.
 Address 208 PETROLEUM BUILDING, WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
C. T. HONAKER, DRIG. SUPT. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker C. T. HONAKER, DRIG. SUPT.
BOX 232, RUSSELL, KANSAS
 (Address)

SUBSCRIBED AND SWORN TO before me this 21ST day of SEPTEMBER, 1962

My commission expires 10-17-63

Jerry Suits
 Notary Public.



CONTINENTAL OIL COMPANY - Operator

SIERRA PETROLEUM CO., INC. - Contr.

BEST HUNTING CLUB #1
 C SE NE
 Sec. 32-21S-11W
 Stafford County, Kansas

T. D.: 3503'

Commenced: 9-7-62
 Completed: 9-19-62

Casing:

8-5/8" Set at 282'

Cement:

with 250 sz. common

FORMATION

DEPTH

Sand & Surface Clay
 Red Bed
 Anhydrite
 Shale
 Shale & Shells
 Shale & Lime
 Lime
 Lime & Chert
 Chert

110
 285
 488
 710
 1275
 2825
 3457
 3482
 3503

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 24 1962
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss:
 COUNTY OF RUSSELL)

I hereby certify that the above information is true
 and correct to the best of my knowledge.

C. T. Honaker
 Drilling Superintendent

Subscribed and sworn to before me this 21st day of September,
 1962.

Gerard Dietz
 Notary Public

My commission expires: 10-17-63