


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 N. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

STAFFORD County. Sec. 34 Twp. 21 Rge. 11 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines S/2 SW SE  
Lease Owner Harms Drilling Company  
Lease Name Eriksen Well No. 1  
Office Address ~~Wichita~~ Box 488 Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 28 19 63  
Application for plugging filed November 28 19 63  
Application for plugging approved November 28 (verbally) 19 63  
Plugging commenced November 28 19 63  
Plugging completed November 28 19 63  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 3525 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	286'	8 5/8"	286'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from total depth to 275' with plug and 25 sacks of cement at this point. Heavy mud to 40' with plug and 10 sacks of cement at this point. 2 sacks of cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 17 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Harms Drilling Company  
Address Box 488 Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Allan Harms (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Allan Harms  
Box 488 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of December, 1963

My commission expires January 22, 1966.

Helen E. Gearhart  
Helen E. Gearhart Notary Public.

D R I L L E R S L O G

COMPANY: HARMS DRILLING COMPANY  
 FARM: ERIKSEN #1  
 COMMENCED: NOVEMBER 19, 1963  
 ELEVATION: 1752 KB

S/2 SW. SE Section 34-21-11W  
 STAFFORD COUNTY, KANSAS  
 COMPLETED: NOVEMBER 28, 1963

0 - 120 sand  
 120 - 450 red bed  
 450 - 473 anhydrite  
 473 - 720 red bed  
 720 - 1250 shell-shale  
 1250 - 1348 shale-lime  
 1348 - 1570 lime & shell  
 1570 - 2200 lime-shale  
 2200 - 2460 shale-lime  
 2460 - 2535 lime-shale  
 2535 - 2785 shale-lime  
 2785 - 2945 lime-shale  
 2945 - 2973 lime  
 2973 - 2978 shale  
 2978 - 2985 lime  
 2985 - 3129 lime-shale  
 3129 - 3406 lime  
 3406 - 3426 conglomerate  
 3426 - 3448 Viola  
 3448 - 3492 Simpson  
 3492 - 3525 Arbuckle  
 3525' Total depth

RECEIVED  
 STATE CORPORATION COMMISSION

DEC 17 1963

CONSERVATION DIVISION  
 Wichita, Kansas

SET 286 feet of 8 5/8 inch surface casing. Cemented with 250 sacks of common cement with 2% calcium chloride.

TOPS: HEBNER - 2973  
 BROWN LIME - 3106  
 LANSING-K.C. - 3130  
 CONGLOMERATE - 3406  
 VIOLA - 3426  
 SIMPSON - 3450  
 ARBUCKLE - 3493

RAN electric log

DRY, Plugged and Abandoned.

A F F I D A V I T

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON )

I, Allan Harms of the Harms Drilling Company being first duly sworn on oath state: I have knowledge of the facts, statements and matters herein contained and the same are true and correct.

Allan Harms  
 Allan Harms

Subscribed and sworn to before me this 16th day of December, 1963.

Helen E. Gearhart  
 Helen E. Gearhart Notary Public

My commission expires: January 22, 1966.