


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Stafford County, Sec. 22 Twp. 21S Rge. 11 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
NE NE SE

Lease Owner Mustang Drilling & Exploration, Inc.  
Lease Name Fair-Sleeper Well No. 1  
Office Address P.O. Drawer 1609, Great Bend, Ks 67530  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole



Locate well correctly on above  
Section Plat

Date Well completed September 27 19 81  
Application for plugging filed September 27 19 81  
Application for plugging approved September 27 19 81  
Plugging commenced September 27 19 81  
Plugging completed September 27 19 81  
Reason for abandonment of well or producing formation

D & A  
If a producing well is abandoned, date of last production 19.

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman, Holyrod, Ks  
Producing formation Depth to top Bottom Total Depth of Well 3550  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE  | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
|           |         |      |    | 8 5/8 | 427    | none       |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

620 ft. 50 sx

250 ft. 30 sx

40 ft. 10 sx

10 sx rathole

5 sx water well

50=50 poz

3% cc; 2% gel


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mustang Drilling & Exploration, Inc.

STATE OF Kansas COUNTY OF Barton, ss.  
Kenneth Roach (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Kenneth O. Roach  
P.O. Drawer 1609, Great Bend, Ks 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of September, 19 81



My commission expires

Beverly Shewbart  
Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 29 1981

CONSERVATION DIVISION  
Wichita, Kansas

OPERATOR: Mustang Drilling & Exploration, Inc.  
 P.O. Drawer 1609, Great Bend, Kansas 67530

WELL: #1 Fair-Sleeper API # 15- 185-21,370

LOCATION: NE NE SE  
 Sec 22 -T21 S-R11W

COMMENCED: September 19, 1981 COMPLETED: September 27, 1981

ELEVATION: GL: 1736 DF: 1738 KB: 1741 TOTAL DEPTH: 3550

CASING: Surface: 8 5/8"; 23 #; set at 427 feet;  
 Cemented with 275 sacks Common cement; 3% cc; 2% gel

Production: - ; - #; set at - feet;  
 Cemented with - sacks - cement;

| DEPTH:      | FORMATION    | FORMATION TOPS           |
|-------------|--------------|--------------------------|
| 0 - 427     | Sand, Redbed | Heebner 2930             |
| 427 - 2036  | Shale, Lime  | Toronto 2948             |
| 2036 - 2400 | Lime, Shale  | Douglas 2960             |
| 2400 - 2500 | Lime         | Brown Lime 3062          |
| 2500 - 2650 | Lime, Shale  | Lansing 3082             |
| 2650 - 2930 | Lime         | Base K.C. 3333           |
| 2930 - 2937 | Shale        | Viola 3356               |
| 2937 - 2960 | Lime         | Simpson 3385             |
| 2960 - 3062 | Shale        | Simpson Sand 3394 - 3409 |
| 3062 - 3340 | Lime         | Arbuckle 3441            |
| 3340 - 3356 | Lime, Shale  | LTD 3551                 |
| 3356 - 3385 | Chert, Lime  | DRLR 3550                |
| 3385 - 3395 | Shale        |                          |
| 3395 - 3410 | Sand         |                          |
| 3410 - 3440 | Shale        |                          |
| 3440 - 3550 | Dolomite     |                          |

DST #1 3088-3118 30-60-30-60  
 20' Mud IHP 1686 IFP 51  
 ICIP 63 FFP 51  
 FCIP 63 FHP 1635  
 Temp. 107°

DST #2 3126-3176 60-60-60-60  
 Strong Blow: 700' SW  
 IHP 1622 IFP 115-204  
 ICIP 1048 FFP 255-319  
 FCIP 1022 FHP 1558  
 Temp. 107°

DST #3 3333-3400 60-60-30-60 Weak Blow  
 150' gas cut mud with spots light oil  
 IHP 1839 IFP 51-76  
 ICIP 933 FFP 89-102  
 FCIP 895 FHP 1839  
 Temp. 109°

ACKNOWLEDGEMENT

STATE OF KANSAS, COUNTY OF BARTON, ss:

Before me, the undersigned, a Notary Public, within and for said county and state, on this 28th day of September, 1981, personally appeared Kenneth Roach to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary deed for the uses and purposes therein set forth.

Subscribed and sworn to before me this 28th day of September, 1981.

My Appointment Expires  
**BEVERLY SHEWBART**  
 Barton County, Kansas  
 Notary Public

Kenneth Roach  
Beverly Shewbart  
 Notary Public