


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Stafford County, Sec. 27 Twp. 21S Rge. (E) 11 (W)

Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner Raymond Oil Co., Inc. & Champlin Oil & Refining
Lease Name Dortha Eriksen Well No. 1
Office Address 410 Fourth National Bank Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed August 7, 19 59
Application for plugging filed August 7, 19 59
Application for plugging approved _____ 19 _____
Plugging commenced August 7, 19 59
Plugging completed August 7, 19 59
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot, St. John, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3537 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to 240 feet with mud. Set plug at 240 feet -
20 sx. cement and 5 sacks hulls. Filled hole to top plug 35 feet.
Set plug with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 18 1960

CONSERVATION DIVISION
WICHITA, KANSAS

1-18-60

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Raymond Oil Company, Inc.
Address 410 Fourth National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Rick P. Clinton (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Rick P. Clinton
410 Fourth Nat'l Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of August, 19 59

My commission expires 5/13/62
Mary Ellen Samyson Notary Public.



Raymond Oil Company, Inc. & Champlin Refining Co.

#1 Dortha Eriksen
 NW NW NW, 27-21S-11W
 Stafford County, Kansas

Elevation: 1743 KB
 1740 DF
 1737 GL

Contractor: Raymond Oil Co., Inc. - Rig #1
 Commenced: July 28, 1959
 Completed: August 7, 1959 (Rotary)

Casing Record:
 8-5/8" @ 293' w/300 sacks

Figures Indicate Bottom of Formation

<u>Formation</u>	<u>Depth</u>
Surface hole, sand	165
Red Bed, shale & shells	293
Red Bed	460
Anhydrite	500
Shale & Shells	1150
Salt	1300
Lime & Shale	2435
Shale & Lime	2665
Lime with Shale	2775
Lime & Shale	3181
Lime	3298
Lime with shale	3362
Chert	3400
Sand	3412
Lime & shale	3418
Shale & Lime	3453
Dolonite	3537
RTD	3537
D & A	

STATE OF KANSAS
 CONSERVATION DIVISION
 JAN 1 8 1960
 Wichita, Kansas

Tops:

Anhydrite	460
Topeka	2657
Heebner	2952
Toronto	2968
Douglas	2986
Brown Lime	3084
Lansing	3101
Conglomerate	3364
Simpson sand	3402
Arbuckle	3453
RTD	3537

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I hereby certify that the above is true and correct to the best of my knowledge.

Rick P. Clinton
 Rick P. Clinton

Subscribed and sworn to before me this 11th day of August, 1959.

Joseph E. Harrison
 Notary Public

My Commission Expires: 5/13/62