


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Blasing Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Stafford County. Sec. 22 Twp. 21 Rge. (E) 14 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE SW $\frac{1}{4}$
Lease Owner Harry Koplin
Lease Name Smith - Colvin Well No. 1
Office Address Chicago, Illinois
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed May 4, 1951
Application for plugging filed May 4, 1951
Application for plugging approved May 4, 1951
Plugging commenced May 4, 1951
Plugging completed May 4, 1951
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top 3784 Bottom 3795 Total Depth of Well 3795 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	237	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

~~XXXXXXXX~~ Cemented hole with Rotary mud, set plug at 330 ft and 15 sacks cement. Top plug at 35 ft. cemented with 10 sacks cement at surface.

STATE CORPORATION COMMISSION
MAY 15 1951
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Armer Drilling Company, Inc.
Address 710 Petroleum Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
L. C. Sponenberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *L. C. Sponenberg*
M 710 Petroleum Bldg, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 11th day of May, 1951.
Hazel Walton
Notary Public.

My commission expires Sept 17, 1951 28-5091-s 8-50-10M

PLUGGING
FILE SEC 22 T 21 R 14
BOOK PAGE 81 LINE 2

LOG

Company: Harry Koplin
 Contractors: Armer Drilling Company, Inc.
 Drilling Commenced: 4/21/51
 Drilling Completed: 5/4/51
 Elevation: 1937 R.B.
 1935 D.F.
 1932 Gr.

Farm: Smith-Colvin Well No. 1
 Location: NE SW SE/4 Sec. 22-21-14W
 Stafford County, Kansas
 Casing records: 8-5/8" OD @ 237 w/175 sacks cement

Sasco rig

(figures below indicate bottoms)

Sand, Shale & Shells	237
Shale & Shells	300
Sand	370
Red Bed & Shale	430
Red Bed & Shale	510
Shale & Shells	580
Anhydrite	870
Shale & Shells	1500
Salt	1610
Lime	2093
Lime & Shale	2155
Shale & Lime	2695
Lime & Shale	2815
Shale & Lime	2977
Lime & Shale	3130
Lime	3292
Lime & Shale	3315
Shale & Lime	3412
Lime	3746
Shale & Lime	3790
Lime	3795
T. D.	3795

FORMATION TOPS

Heabner	3290
Brown Lime	3410
Lansing - Kansas City	3421
Viola	3698
Simpson	3747
Arbuckle	3781
T. D.	3795
D & A	

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

ARMER DRILLING COMPANY, INC.

RECEIVED
 STATE CORPORATION COMMISSION

MAY 15 1951

CONSERVATION DIVISION
 WICHITA, KANSAS

J. W. Speer

STATE OF KANSAS

COUNTY OF SEDGWICK

ss:

Subscribed and sworn to before me, a notary public, in and for said County and State this 10th day of May, 1951.

PLUGGING
 NE SEC-21-21-14W
 BOOK PAGE 21 LINE 21

Raye Walter
 Notary Public

My commission expires Sept. 17, 1951.