

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 22 Twp. 21S Rge. (E) 14(W)

Location as "NE/CNW&SW" or footage from lines SW NW SW

Lease Owner Time Petroleum Company

Lease Name Meier Well No. 1

Office Address 815 Union National Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 14 19 64

Application for plugging filed November 14 19 64

Application for plugging approved November 14 19 64


Plugging commenced November 14 19 64

Plugging completed November 14 19 64

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie V. Elving, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3740 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TD	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	272'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole as follows: Plugged at 260' ran 25 sacks of cement through the drill pipe and mud to 40'; plugged with 10 sacks of cement and 1/2 sack of hulls. Also plugged the rat hole with 3 sacks of cement and 2 sacks of cement in the mouse hole. Job completed at 2:30 A. M. November 14, 1964.

RECEIVED
STATE CORPORATION COMMISSION

NOV 19 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.

Address P. O. Box 355, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Jim B. McWilliams (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim B. McWilliams, Secy-Treas.

P. O. Box 355, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of November, 19 64

Elaine H. Taylor, Notary Public.

My commission expires December 14, 1965

DRILLERS LOG

#1 Meier

CASING RECORD: Ran 263.58' of used 8-5/8" casing.
 COMPANY: Time Petroleum Company
 DESCRIPTION: SW NW SW Section 22-T21S-R14W Stafford County, Kansas
 CONTRACTOR: Strata Drilling, Inc.
 TOTAL DEPTH: 3740'
 COMMENCED: November 5, 1964
 ELEVATION: 1943' RB
 COMPLETED: November 14, 1964

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	240	Ran 263.58' of used 8-5/8" surface casing; set and cemented at 272' with 250 sacks of regular cement, 2% gel and 3% calcium chloride. Cement did not circ.. Ran 42 sacks of regular cement through 1" tubing. Plug down at 12:30 A. M. November 6, 1964.
Shale	240	272	
Shale & Sand, Red Bed	272	425	
Red Bed	425	858	
Anhydrite	858	981	
Shale & Shells	981	1715	
Shale & Lime	1715	3465	
Lime	3465	3660	
Lime, Shale & Chert	3660	3740	

Total Depth 3740'

Ran two drill stem tests.

D. & A.

Plugged hole as follows: Plugged at 260' ran 25 sacks of cement through the drill pipe and mud to 40'; plugged with 10 sacks of cement and 1/2 sack of hulls. Also plugged rat hole with 3 sacks of cement and 2 sacks of cement in the mouse hole. Job completed at 2:30 A. M. November 14, 1964.

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 19 1964
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss.
 COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Jim B. McWilliams
 Jim B. McWilliams, Secy-Treas.

Subscribed and sworn to before me this 17th day of November, 1964.

Elaine H. Taylor
 Elaine H. Taylor, Notary Public

My Commission Expires:

December 14, 1965