


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Take Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Stafford County, Sec. 22 Twp. 21S Rge. 14 (E) (W) X

Location as "NE/CNW%SW%" or footage from lines NW SE NE
Lease Owner Aspen Drilling Company
Lease Name Strobel Well No. 1
Office Address P. O. Box 783 Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 4-24-68 19
Application for plugging approved 4-25-68 19
Plugging commenced 6-14-68 19
Plugging completed 6-29-68 19
Reason for abandonment of well or producing formation



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3780 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	278	None
				5 1/2	None	3026

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in. Cleaned out cellar.

Sanded to 3750'. Dumped 5 sacks of cement. Rigged up unit. Working pipe.

Working pipe. Shot pipe at 3010'. Circulating. Spotted 55 bbl of oil.

Working pipe. Pulling pipe.

Squeezed well with 15 sacks of mud and 90 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 8 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 3 day of July, 19 68

My commission expires May 27, 1969 Notary Public.

D R I L L E R S L O G

COMPANY Aspen Drilling Co.
 CONTRACTOR Aspen Drilling Co.
 LEASE NAME Strobel #1
 LOCATION NW SE NE Sec.22-T21S-R14W
 Stafford County, Kansas
 ELEVATION 1936 DF
 SURFACE CASING 14 jts. (278') 8 5/8"
 OIL STRING 119 jts. 5 1/2"
 COMMENCED November 14, 1966
 COMPLETED November 25, 1966
 ROTARY TOTAL DEPTH 3780'

<u>FORMATION</u>	<u>DEPTH</u>	
Sand	130	Spudded in 12 1/4" hole at 5:00 PM
Shale	345	11-14-66. Ran 14 jts. (278')
Sand	770	8 5/8" casing, set at 286', cemented
Red-Bed	847	with 225 sacks Sunset, cement
Anhydrite	870	circulated. Plug down. 12:00 PM.
Shale	1680	
Shale & lime	1830	DST #1 3422 - 3486
Lime	2089	DST #2 3565 - 3597
Shale & lime	3080	DST #3 3680 - 3725
Lime & Shale	3272	DST #4 3775 - 3780
Lime	3313	
Shale	3400	Ran Laterolog-Gamma Ray-Neutron
Brown Line	3410	
Lansing	3465	Ran 119 jts. 5 1/2" casing, set at
Lime	3678	3775', cemented with 125 sacks
Chert	3695	50/50 Pozmix, 20% gel. Plug
Chert-Lime	3725	down 1:40 AM. 11-25-66
Lime	3730	
Simpson	3765	
Lime-Arbuckle	3780	

FORMATION TOPS

Anhydrite	847
Base Anhydrite	869
Heebner	3278
Toronto	3301
Douglas	3319
Brown Lime	3397
Lansing	3408
Base Kansas City	3615
Viola	3674
Simpson	3719
Arbuckle	3772
Log T.D.	3778

RECEIVED
 STATE CORPORATION COMMISSION
 APR 25 1968
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
 COUNTY OF BARTON) ss:

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.

William S. Schachle
 William S. Schachle

Subscribed and sworn to before me this 15th day of December, 1966.

Thomas Holloman
 Notary Public

My commission expires: April 18, 1968