

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 20 Twp. 21 Rge. 14 ~~XX~~ W (W)

Location as "NE/CNW%SW%" or footage from lines NW NE NE

Lease Owner D.R. Lauck Oil Company, Inc & Sunray Mid-Continent

Lease Name Brown Well No. 1

Office Address 301 South Broadway Wichita 2 Kans

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed May 13 1956

Application for plugging filed May 13 1956

Application for plugging approved May 13 1956


Plugging commenced May 13 1956

Plugging completed May 13 1956

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. R. M. Brundege

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3790 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		870	0	8 5/8	870	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

_____ mud 3790-300'

_____ plug 300-296

_____ cement 296- 35

_____ plug 35- 31

_____ cement 31- 6 bottom of cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Globe Oil Well Cementing Co.

Address Great Bend Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
John H. Knightley (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John H. Knightley
Wichita Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of May, 1956

My commission expires Sept. 14, 1959

Elizabeth May
Notary Public.

PLUGGING
FILE SEC. 20 T. 21 R. 14W
BOOK PAGE 61 LINE 26

MAY 23 1956
COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

D. R. Laučk Oil Company, Inc.
and Sunray Mid-Continent Oil Company

NW NE NE Sec. 20-21S-14W
Stafford County Kansas

Brown No. 1

Commenced: May 1 1956
Completed: May 13, 1956

Elevation: GR 1937; DF 1939; KB 1941;

Casing Record: 870' 8 5/8" cemented w/400 sacks

Drillers Log

Tops

Halliburton

Sand & Clay	185	Anhydrite	865+1076	
Clay and Sand	220	Heebner	3274-1333	3275-1334
clay & Blue Shale	300	Brown lime	3389-1448	3391-1450
sand	305	Lansing K C	3401-1460	3403-1462
red bed & shale	865	Base KC	3628-1687	3622-1681
Anhydrite	890	Viola	3661-1720	3666-1725
red bed & shale	1345	Simpson shale	3700-1759	3704-1763
salt & shale	1425	Simpson sand	3717-1776	3721-1780
shale & lime	1760	Arbuckle	3749-1808	3754-1813
lime & shale	2135	Rotary Total Depth	3790-1849	3794-1853
lime	2255			
lime & shale.	2500	DST #1	3662-3677 weak blow 5 min; open 30"; recovered 5' mud; BHP 0# 30 min.	
shale & shells	2795	DST#2	3718-3723 open 1 hour; strong blow 1 hr.; recovered 496' salt water w/scum of oil; IFP 60#; FFP 500#; BHP 1012# in 30 min;	
shale & lime	3145	DST #3	3750-3754 open 30 ", weak inter- mittent blow; recovered 40' watery mud; IFP 0#; FFP 0#; BHP 1120# in 30 min.	
lime	3335	DST#4	3550-3574 After Elec. Log; open 30", weak blow 8 min; recovered 8' mud; IFP 10#; FFP 10#; BHP 80# in 20 min.	
shale	3388			
Lime	3655			
shale & lime	3661			
Viola chert	3715			
sand	3723			
lime & shale.	3745			
lime	3790			
Rotary Total Depth	3790			

D & A.

PLUGGING	
FILE	SEC. 20. T. 21. R. 14w
BOOK	PAGE 61 LINE 26

[Faint circular stamp, possibly a company or date stamp]