

State of Kansas



15-159-05504-0000

WM. H. AYERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

August 15, 1966

RECEIVED
STATE CORPORATION COMMISSION
AUG 25 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Owen Bailey of Santa Fe Pipe & Supply, Inc. has this date requested permission to plug the following described well:

Mr. Bailey guarantees payment of the plugging fee.

Operator's full Name: Santa Fe Pipe & Supply, Inc.

Complete Address: P.O. Box 562, Great Bend, Kansas

Lease Name: McFarland Well No. 1

Location: NE SW SW Sec. 3 Twp. 21 Rge. 8 ~~(E)~~ (W) X

County Rice Total Depth 3344' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Bailey was instructed to plug the well as follows:

Fill hole with sand to 3290' and cement with 5 sacks.

Fill hole with mud to 265'. Set rock bridge from 265' to 255' and

cement hole with 20 sacks. Fill hole with mud to 40'. Set rock bridge

from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

William L. Mitchell
Conservation Division Agent