



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

RECEIVED  
APR 4 1982  
STATE CORPORATION COMMISSION

APR 12 1982  
CONSERVATION DIVISION  
Wichita, Kansas

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Tom Meyers of Sterling Drilling Co. has this 4-14-82 date requested permission to plug the following described well:

Operator's Full Name: Sterling Drilling Company

Complete Address: P.O. Box 129, Sterling, Kansas 67579

Lease Name: Richter Well No. 1

Location: C 5/2 NE SE Sec. 7 Twp. 21 Rge. 8 (E) (W)

County: Rice Total Depth: 3560'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Meyers was instructed to plug the well as follows:

Circulate hole and fill with mud. Pump 50 sacks cement through  
drill pipe at 300'. Fill hole with mud to 40'. Push plug and  
1/2 sack hulls to 40' and cap hole with 10 sacks cement.  
Cement rat hole with 10 sacks cement through pipe

Very truly yours,

Conservation Division Agent