



15-113-30022-0000

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

May 6, 1965

RECEIVED
STATE CORPORATION COMMISSION

MAY 10 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Herb. Mason of Dunne-Gardner Drlg. Co., has this

date requested permission to plug the following described well:

Mr. Mason guarantees payment of the plugging fee.

Operator's full Name: Dunne-Gardner Drilling Co., Inc.

Complete Address: 300 Schweiter Bldg., Wichita, Kansas

Lease Name: N. Krehbiel Well No. 1

Location: SE SW NE Sec. 27 Twp. 21 Rge. 2 (E) (W) X

County Mc Pherson Total Depth 3430' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mason was instructed to plug the well as follows:

Fill hole with mud to 235'. Push plug and 1/4 sack hulls to 235' and cement hole with 20 sacks through drill pipe.

Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,

Arthur J. Loman
Conservation Division Agent