

(Copy)

State of Kansas



15-159-00674-0000 FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

March 20, 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Sylvester Fickel of Red Tiger Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Fickel guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling Inc.

Complete Address: 712 Union Center, Wichita, Kansas

Lease Name: Fair "D" Well No. .1

Location: NE SW NE Sec. 27 Twp. 21 Rge. 10 (E) (W) X

County Rice Total Depth 3490' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Fickel was instructed to plug the well as follows:

Circulate heavy mud. Fill hole with mud to 235'. Push

plug and 1/4 sack hulls to 235' and cement hole with 20

sacks, through drill pipe. Fill hole with mud to 35'.

Push plug and 1/4 sack hulls to 35' and cap hole with 10

sacks cement Bridge, and cement rathole with 2 sacks.

APR 19 1963

Very truly yours,

CONSERVATION
Wichita, Kan.

Robert J. Roman
Conservation Division Agent