



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

March 14, 1970

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 17 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Frank Neff of Nadel & Gussman has this date requested permission to plug the following described well:

Mr. Neff guarantees payment of the plugging fee.

Operator's full Name: Nadel & Gussman

Complete Address: 1714 First Nat'l Bldg., Tulsa, Oklahoma

Lease Name: Sleeper Well No. 1

Location: SW SW Sec. 35 Twp. 21 Rge. 10 XE (W) X


County: Rice Total Depth 3600' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Neff was instructed to plug the well as follows:

Fill hole with mud to 245'. Push plug and 1/4 sack hulls to 245' and  
cement hole with 25 sacks cement through drill pipe. Fill hole with  
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10  
sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

  
Conservation Division Agent