



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 27 1972

CONSERVATION DIVISION  
Wichita, Kansas

10-27-1972

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Michael of Coin Petro. has this

date requested permission to plug the following described well:

Mr. Micheal guarantees payment of the plugging fee.

Operator's full Name: Coin Petro & Hinkle Oil Co.

Complete Address: 220 W. Douglas, Wichita, Kansas

Lease Name: Lynam Well No. 1

Location: NW NE Sec. 34 Twp. 21 Rge. 21 XX (E) (W)

County: Hodgeman Total Depth 4400' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Michael was instructed to plug the well as follows:

8 5/8" to 405' circulated w/ cement. Mud 4400' to 800'

Spotted 100 sacks cement 800' to 500' Mud 500' to 375'

Spott 30 sacks cement 375' to 275' Mud 275' to 40'

Plug, Halls & 10 sacks cement 40' to 0'.

Very truly yours,

Conservation Division Agent