



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 12 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Steincamp of Kaiser-Franis has this

date requested permission to plug the following described well:

Mr. Steincamp guarantees payment of the plugging fee.

Operator's full Name: Kaiser-Franis

Complete Address: 4120 E 51st Street, Tulsa, Oklahoma

Lease Name: Stueckmann "A" Well No. 1

Location: C NW NW Sec. 30 Twp. 21 Rge. 21 ~~(E)~~ (W)

County: Hodgeman Total Depth 4507' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Steincamp was instructed to plug the well as follows:

- 8 5/8" to 255' circulated w/ cement. Mud 4507' to 850'
- Spot 80 sacks cement 850' to 550' Mud 550' to 200'
- Spot 30 sacks cement 200' to 100' Mud 100' to 45'
- Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent