



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 9 1972

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Elmore of Tesoro has this

date requested permission to plug the following described well:

Mr. Elmore guarantees payment of the plugging fee.

Operator's full Name: Tesoro Petroleum Corp.

Complete Address: Box 3305, Bartlesville, Oklahoma

Lease Name: Plummer Well No. 1-A

Location: NW SW Sec. 35 Twp. 21 Rge. 38 <sup>XX</sup>(E)(W)

County: Kearny Total Depth 5354' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Elmore was instructed to plug the well as follows:

8 5/8" to 1107' circulated w/ cement. 5 1/2" to 5133' cemented.

Top perforations 5070' Plug bottom w/ 20 sacks cement.

Top of cement 4900' Mud 4900' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 450'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent