



15-075-10045-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 22 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Sargent of Humble Oil has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Humble Oil & Refining Company

Complete Address: 2000 Classen Center, Oklahoma City, Oklahoma

Lease Name: Forrest Smith Unit Well No. 1

Location: NE SW Sec. 6 Twp. 21 Rge. 40 (E)(W)

County Hamilton Total Depth 2813' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 389' circulated w/ cement. 4 1/2" to 2801' cemented.

Top perforations 2794' Plug bottom w/ 50 sacks cement.

Top of cement 2237' Mud 2237' to 2180'

Spot 50 sacks cement 2180' to 2070' Mud 2070' to 439'

Spot 50 sacks cement 439' to 300' Mud 300' to 40'

Plug, Halls & 10 sacks cement 40' to 0'.

Very truly yours,

Edward J. Eves
Conservation Division Agent