



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Sam Lyons of Higginbottom Eng. has this date requested permission to plug the following described well:

Operator's Full Name: Petro Mark. Exploration

Complete Address: Box 6 Liberal, Kans. 67901

Lease Name: Pina Well No. #1

Location: C-SE-NW Sec. 32 Twp. 21^S Rge. 29^W (E) (W)

County: Hamilton Total Depth: 2825^{FE}

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Lyons was instructed to plug the well as follows:

8 5/8" - 369^{FE} SP. cm. 275ST ent. -> 4 1/2" Set @ 2825^{FE} 550ST ent.

Plug Back T.D. 2820^{FE} Recp. 2770^{FE} to 2780^{FE} - no Pipe Recovery

Ordered 120ST 50% Forming 4% Gel. 3% G.L. -> 5ST Gel. -> 1ST shells.

and 4 1/2" Plug. Pumped In with Pump Truck.

Pumped In Annulus 30ST ent. - May Pressure 550^{PSI} -> Pumped In 4 1/2"

1ST shells. -> 35ST ent. -> 5ST Gel. - Released Plug and 115ST ent. May Pressure

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours, (By Drwell) 1500^{PSI}

JUN 10 1982

CONSERVATION DIVISION
Wichita Kansas

Marvin Johnson
Conservation Division Agent