

State of Kansas



15.159-30218-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

February 11, 1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

FEB 16 1966

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Clarence Michaels of Sage Drilling Company, Inc. has this

date requested permission to plug the following described well:

Mr. Michaels guarantees payment of the plugging fee.

Operator's full Name: Wayne Merchant

Complete Address: 227 Beacon Bldg., Wichita, Kansas

Lease Name: Wilkey Well No. 1

Location: SE SW NW Sec. 8 Twp. 21 Rge. 8 (W) X

County Rice Total Depth 3480' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Michaels was instructed to plug the well as follows:

Fill hole with mud to 180'. Push plug and 1/4 sack hulls to 180' and
cement hole with 20 sacks through drill pipe. Fill hole with mud to
40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

Conservation Division Agent