

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 27 1972

CONSERVATION DIVISION
Wichita, Kansas

10-29-1992

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Coin Petroleum & Hinkle Oil Company

Complete Address 214 Pg Court, 220 W. Douglas, Wichita, Kansas.

Lease Name Lymam Well No. 1

Location NW NE Sec. 34 Twp. 21 Rge. 21 (E) (W)

County Hodgeman Total Depth 4400'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Sage Drilling Co.

Address Wichita, Kansas License No.

Operation Completed: Hour 3:30AM Day 24 Month 10 Year 1972

The above well was plugged as follows:

8 5/8" to 405' circulated w/ cement. Mud 4400' to 800'

Spotted 100 sacks cement 800' to 500' Mud 500' to 375'

Spotted 30 sacks cement 375' to 275' Mud 275' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'. Sun Cementing Pump Truck.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Evers
Well Plugging Supervisor

INVOICED

DATE 10/27/72

INV. NO. 6540-U