

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 9 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Tesoro Petroleum Corporation

Complete Address Box 3305, Bartlesville, Oklahoma

Lease Name Plummer Well No. 1-A

Location NW SW Sec. 35 Twp. 21 Rge. 38 (E) (W)

County Kearny Total Depth 5354'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Sargents Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 4:00PM Day 4 Month 8 Year 1972

The above well was plugged as follows:

8 5/8" to 1107' circulated w/ cement. 5 1/2" to 5133' cemented.

Top perforations 5070' Plug bottom w/ 20 sacks cement.

Top of cement 4900' Mud 4900' to 900'

Spotted 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump

Pulled 3608' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed:
Well Plugging Supervisor

DATE 8-10-72

INV. NO. 6136-W