

KANSAS

**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 22 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Humble Oil & Refining Company

Complete Address: 2000 Classen Center-N. Bldg., Oklahoma City, Oklahoma

Lease Name Forrest Smith Unit Well No. 1

Location NE SW Sec. 6 Twp. 21 Rge. 40 (W)

County Hamilton Total Depth 2813'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: None

Plugging Contractor: Sargent Casing Pulling Co.

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 11:00 AM Day 18 Month 7 Year 1968

The Above well was plugged as follows:

8 5/8" to 389' circulated w/ cement. 4 1/2" to 2801' cemented  
Top perforations 2794' Plug bottom w/ 50 sacks cement  
Top of cement 2237' Mud 2237' to 2180'  
Spotted 50 sacks cement 2180' to 2070' Mud 2070' to 439'  
Spotted 50 sacks cement 439' to 300' Mud 300' to 40'  
Plug, Halls & 10 sacks cement 40' to 0' Company Pump  
Pulled 2220' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 7-23-68  
INV. NO. 8174-W

Signed: [Signature]  
Well Plugging Supervisor