

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 131-37LOCATION SW $\frac{1}{4}$ - NW $\frac{1}{4}$ - SW $\frac{1}{4}$ SEC. 21 TWP. 21 RGE. 1WDry Hole Abandoned Oil Well ☒ Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 3 Lease BlairOperator Continental Oil Co. Address RFD 4, Lyons Kans.Field County McPhersonTotal Depth 3332 Feet.Plugging Contractor West Supply Co.Plugging Contractor's License No. 14Address Chase Kansas

(Describe briefly the manner in which the well was plugged)

Surface pipe 12 $\frac{1}{2}$ " @ 140' C.W.C.
Filled hole back with sand to 3310 and dumped
6 sq of Cem. with dump trailer. Shot off and
pulled 7" casing @ 2400' Filled hole with mud
to 145' Set 10' rock bridge and mixed and run
25 sq of Cem. mudded hole to 30' rock bridge
and 8 sq of Cem. to surface to complete plugging

RECEIVED
STATE CORP. COM.
DIVISION

OCT 17 1953

CONSERVATION DIVISION
Wichita, Kansas

Warren H. Garner
District Conservation Agent

Date 10-15-53

PLUGGING	
FILE	SEC. <u>21</u> T. <u>21</u> R. <u>1W</u>
BOOK	PAGE <u>131</u> LINE <u>32</u>