

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15,075.30095.0000

API NUMBER Not Issued

LEASE NAME 1311 Bengston

WELL NUMBER 1-D

3300 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 13 TWP. 21S RGE. 41 (E) or (W)

COUNTY Hamilton

Date Well Completed 12/07/65

Plugging Commenced 1/09/86

Plugging Completed 1/09/86

LEASE OPERATOR Plains Petroleum Company

ADDRESS P.O. Box 15278, Lakewood, CO 80215

PHONE# (303) 969-9323 OPERATORS LICENSE NO. 4253

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #1, Dodge City, KS

Is ACO-1 filed? Yes If not, is well log attached? N/A

Producing Formation N/A Depth to Top Perfs 2364' Bottom Perfs 2448' T.D. 2497'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Not Available				8-5/8"	391'	0'
				2-7/8"	2497'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

The disposal well at the above location is piggy backed inside the surface casing with the production casing. For this reason, no attempt was made to recover any pipe. In plugging this disposal well, a 1 1/2" string of tubing was run to hard bottom and cement plugs were pumped as the tubing was pulled out (continued on back).

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Dowell-Schlumberger Services License No. N/A

Address P.O. Box 887, Ulysses, KS 67880

STATE OF COLORADO COUNTY OF Denver, ss.

Lee Brian VanRamshorst (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 15278, Lakewood, CO 80215

SUBSCRIBED AND SWORN TO before me this 28th day of January, 19 86

Karen L. Robineau
Notary Public

My Commission Expires: March 12, 1986

RECEIVED
STATE CORPORATION COMMISSION
Form CP-4
JAN 31 1986
Revised 08-84

1-31-86

15.075.30095.0000

1½" tubing was set at 2394' and cement was pumped from 2394' to 1531'. The 1½" was pulled up-hole and set at 1554', cement was pumped from 1531' to 668', the 1½" was pulled up to 672', and cement was circulated to surface. The 1½" was pulled up to 168' and cement was circulated to surface. The 1½" tubing was pulled out of the hole, and the wellbore was filled completely with cement from surface. the cement was mixed and pumped by Dowell-Schlumberger Services from Ulysses, KS. A total of 75 sacks of 60/40 poz mix with 2% gel was used to plug this well.

RECEIVED
STATE CORPORATION COMMISSION

JAN 31 1985

CONSERVATION DIVISION
Wichita, Kansas