

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 1 S. Market, Room 2078
 Topeka, KS 66602
 KANSAS CORPORATION COMMISSION

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-075-10055-00-00

LEASE NAME HCU

WELL NUMBER 1111

1980' Ft. from S Section Line

1980' Ft. from ^W Section Line

SEC. 11 TWP. 21 RGE. 41 (S) or (W)

COUNTY Hamilton

Date Well Completed 12/8/63

Plugging Commenced 6-14-01

Plugging Completed 6-15-01

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

JUL 20 2001

OPERATOR Louis Dreyfus Natural Gas Corp

ADDRESS 14000 Quail Springs Parkway - Okla City OK 73134

PHONE (405) 749-1300 OPERATORS LICENSE NO. 31321

Character of Well _____

(i.e., Gas, Oil, SWD, Input, Water Supply Well)

* plugging proposal was approved on 6-13-01 (date)

Kevin Strabe (KCC District Agent's Name)

ACD-1 filed? Yes If not, is well log attached? _____

Producing Formation Winfield Depth to Top 2766' Bottom 2777' T.O. 2796'

Show depth and thickness of all water, oil and gas formations.

WELL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|--------------|-------------|------------|
| | | | | <u>8 7/8</u> | <u>169</u> | <u>-</u> |
| | | | | <u>4 1/2</u> | <u>2795</u> | <u>587</u> |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was added and the method or methods used in introducing it into the hole. If cement or other plug was used, state the character of same and depth placed, from _____ feet to _____ feet each so
Ran 2 3/4 & 2 1/2 to 2700. Circ. hole w/mud & mixed 1 5/8 hulls & 20 sx cont. to plug
Perfs from 2766 to 2566. Recovered 587 4 1/2 & 70H w/4 1/2 Ran 2 3/4 to 625 Circ. 1616
w/mud & mixed 80 sx 625 to 400 Pull to 200 40 sx 200 to 80 Pull to 40 10 sx 40 to 0
Cut off & capped 8 7/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

Name of Party Responsible for Plugging Fees: Louis Dreyfus Natural Gas Corp

State of Okla County of Okla, ss.


Lenora Sawyer (Employee of Operator) or (Operator)
 do hereby certify that I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Lenora Sawyer

(Address) 14000 Quail Springs Parkway

AND SWORN TO before me this 18th day of July, 2001

Barrie A. Renfro
 Notary Public



Expires: 9-01-01

OK