

130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record

K.A.R. -82-3-117

RECEIVED

API NUMBER

15-185-23159-0000

LEASE NAME

H. Debes

WELL NUMBER

1-8

TYPE OR PRINT

NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

JUL 26 2002
7-26-2002
KCC WICHITA

1940 Ft. from South Line of Section
620 Ft. from West Line of Section

LEASE OPERATOR F.G. Holl Company, L.L.C. SPOT LOCATION 40' S of Nw Sw
ADDRESS P.O. Box 780167 Section 8 Township 21s Range 14w
CITY, STATE, ZIP Wichita, Kansas 67278-0167 County Stafford
PHONE # 316-684-8481 Date Well Completed July 24, 2002
Character of Well Dry and Abandoned Date Plugging Commenced July 24, 2002
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed July 24, 2002

The plugging proposal was approved on July 23, 2002 at 2:00 pm (date)
by Steve Middleton (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 3775

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	180			
Redbeds	Shale	180	821			
Anhydrite		821	847			
Redbeds and Shales		847	857	8-5/8"	846'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Received plugging orders 07/23/02 from Steve Middleton. Plugged on 07/24/02 in following manner;

135 sx of 60/40 Poz, 6% Gel; Heavy mud in hole and between all plugs. Bottom plug at 3686'-40 sx.

2nd plug at 880'-50 sx. 3rd plug at 230'-20 sx. Top plug at 40'-10 sx cemented to surface.

Rathole-15 sx. No mousehole. Plug down at 1:00 pm on 07/24/02. Acid Services ticket #4866.

Name of Plugging Contractor Sterling Drilling Company

Licence No. 5142

Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl Company, L.L.C. (Operator)

STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first


duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) Gary M. Talbott
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 25th day of July, 2002

Pamela S. Fields
(Notary Public)



My Commission Expires: _____

OR

Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

RECEIVED
JUL 26 2002
KCC WICHITA

SAMPLE LOG

H. Debes 1-8

LOCATION: 40' S of Nw Sw Section 8 T 21s R 14w
API: 15-185-23159-0000 Stafford County, Kansas

OWNER: F.G. Holl Company, L.L.C.
CONTRACTOR: Sterling Drilling Company, Rig #1

COMMENCED: 15-Jul-02
COMPLETED: 24-Jul-02

TOTAL DEPTH: **DRILLER** 3775 FEET
LOGGER 3775 FEET

Ground Elevation: 1931
KB Elevation: 1940

LOG

0 -	2 FEET	Top Soil
2 -	17 FEET	Clay
17 -	25 FEET	Sand and Gravel
25 -	32 FEET	Clay
32 -	74 FEET	Sand and Gravel
74 -	821 FEET	Redbeds
821 -	847 FEET	Anhydrite
847 -	1810 FEET	Redbeds, Shales and Salt
1810 -	3686 FEET	Limestone, Shale and Dolomite
3686 -	3775 FEET	Arbuckle

CASING RECORDS

Surface Casing-8-5/8"

Spud at 12:45 pm on 07/15/02. Drilled 12-1/4" hole to 857'. Ran 20 joints of new 23# 8-5/8" surface casing, tally 846' set at 857' KB. Cemented with 210 sx A-Con; 3% CC, 1/4# Celloflake, and 125sx common; 2% Gel, 3% CC and 1/4# Celloflake. Cement did circulate.
Plug down at 4:30 am on 07/16/02 by Acid Services. Ticket #4956.

Plugging Data

Received plugging orders 07/23/02 from Steve Middleton. Plugged on 07/24/02 in following manner;
135 sx of 60/40 Poz, 6% Gel; Heavy mud in hole and between all plugs. Bottom plug at 3686'-40 sx.
2nd plug at 880'-50 sx. 3rd plug at 230'-20 sx. Top plug at 40'-10 sx cemented to surface.
Rathole-15 sx. No mousehole. Plug down at 1:00 pm on 07/24/02. Acid Services ticket #4866.

DEVIATION SURVEYS

1/2	degree(s) at	857	feet
3/4	degree(s) at	1850	feet
1/2	degree(s) at	2443	feet
3/4	degree(s) at	3525	feet
1/4	degree(s) at	3775	feet