

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Hodgeman SEC. 35 TWP. 21 RGE. 21 N/W
Location as in quarters or footage from lines:
NE SE

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

Lease Owner PETX Petroleum Corp.
Lease Name Dresie Well No. 1
Office Address 1616 Glenn Armn Place, # 1804, Denver, Colo. 80202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed April 17, 1981
Application for plugging filed Verbal Application
Plugging commenced April 17, 1981
Plugging completed April 17, 1981
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas, Jr.

Producing formation _____ Depth to top _____ bottom T.D. 4,500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

| Formation | Content | From | To | Size | Put in | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 328' | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,500 ft. (rotary total depth) to 1,725ft. Set plug at 1,725ft. and cemented with 35 sacks cement.
Filled hole with heavy rotary mud from 1,725 ft. to 1,600ft. Set plug at 1,600ft. and cemented with 35 sacks cement. Filled hole with heavy rotary mud from 1,600ft. to 320' ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Sun Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing Co.

RECEIVED
STATE CORPORATION COMMISSION

MAY 8 1981

STATE OF Kansas COUNTY OF Sedgwick, ss.

Gary Younger, agent (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

CONSERVATION DIVISION
KANSAS
5-8-81

(Signature) Gary Younger
251 N. Water, #10, Wichita, Ks.
(Address) 67202



SUBSCRIBED AND SWORN TO before me this 6th day of May, 19 81

Elsie Willison
Elsie Willison - Notary Public.

My Commission expires: July 25, 1982

