

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Hodgeman County, Sec. 34 Twp. 21S Rge. (E) 21Ww

Location as "NE/CNW/SW" or footage from lines C NW NE
Lease Owner Coin Petroleum Co. & Hinkle Oil Co.
Lease Name Lynam Well No. 1
Office Address 214 Page Court, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 24, 1972
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced October 24, 1972
Plugging completed October 24, 1972
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Edgar Eves of Sublette)

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4355 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Casing	0	401'	8-5/8"	401'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 800 Feet,
110 sax Cement from 800 Feet to 500 Feet;
Mud to 375 Feet, 30 sax Cement to 275 Feet;
Mud to 40 Feet, Plug Bridged and 10 sax
Cement to Base of Cellar; 2 sax Cement in
Rat Hole. Job completed @ 5:00 A.M.

RECEIVED
STATE CORPORATION COMMISSION
OCT 30 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing, Inc.
Address Box 169, Great Bend, Kansas 67530


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Clarence Michael of Sage Drilling Co. (employee of owner) or (owner or operator) of the above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clarence Michael
500 Bitting Bldg., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of October, 1972.

Louise K. Whitted
Louise K. Whitted - Notary Public.

My commission expires November 26, 1974.



RECEIVED
STATE CORPORATION COMMISSION

OCT 30 1972

CONSERVATION DIVISION
Wichita, KansasDRILLERS LOGLYNAM NO. 1

CASING RECORD:	OPERATOR:	Coin Petroleum Co. & Hinkle Oil Co.	DESCRIPTION:
8-5/8" @ 401'			C NW NE
3/275 sax cement	CONTRACTOR:	Sage Drilling Co.	Sec. 34-21S-21W
			Hodgeman County,
TOTAL DEPTH:	COMMENCED:	October 14, 1972	Kansas
4355'	COMPLETED:	October 24, 1972	ELEVATION: 2126KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil, Shale & Sand	0	190	
Shale, Sand & Shells	190	405	
Shale	405	705	
Sand	705	925	
Shale & Sand	925	1276	
Anhydrite	1276	1305	
Shale	1305	1870	
Shale & Lime	1870	2200	
Lime	2200	2215	
Lime & Shale	2215	2560	
Lime	2560	2665	
Lime & Shale	2665	3610	
Lime	3610	4355	D&A

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

BY Clarence Michael
Clarence Michael

Subscribed and sworn to before me this 26th day of October, 1972.



Louise K. Whitted
Louise K. Whitted - Notary Public

My commission expires:
November 26, 1974.