

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-075-20110-0000

LEASE NAME GRILLIOT

WELL NUMBER 2

SPOT LOCATION _____

SEC. 3 TWP. 21^S RGE. 40 (X) or (W)

COUNTY HAMILTON

Date Well Completed 11-1-75

Plugging Commenced 3-21-86

Plugging Completed 3-21-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR TEXACO INC.
FOR TEXACO OILS INC.

ADDRESS BOX 2420, TULSA, OKLAHOMA

PHONE # 918, 560-6000 OPERATORS LICENSE NO. 5153

Character of Well GAS
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? DISTRICT #1, DODGE CITY, KANSAS

Is ACO-1 filed? YES If not, is well log attached? _____

Producing formation U. WINFIELD Depth to top 2807' bottom 2812' T.D. 2850'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	321	NONE
				4 1/2	2842	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. From 2812 to 2569 w/15 sx ce; from 2569 to 2400 w/mud; from 2400 to 2076 w/20 sx ce; from 2076 to 1500 w/mud; from 1500 to 1013 w/20 sx ce; from 1013 to 350 w/mud; from 350 to 188 w/10 sx ce; from 188 to 40 w/mud; from 40 to 3 w/ 4 sx ce; from 3 to GL w/dirt

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Company Tools License No. _____
Address _____

STATE OF Oklahoma COUNTY OF Tulsa, ss.

R. W. Blohm (employee of operator)

~~copy~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. W. Blohm

(Address) BOX 2420, TULSA, OKLAHOMA

SUBSCRIBED AND SWORN TO before me this 19th day of May, 1986

Deborah M. Roberson
Notary Public

My Commission expires: 8/3/88

STATE CORPORATION COMMISSION
MAY 21 1986
CONSERVATION DIVISION
Wichita, Kansas