


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Rice County. Sec. 1 Twp. 21 Rge. 8 (E) 8 (W)  
Location as "NE/CNWSW" or footage from lines NW/4 SW/4  
Lease Owner Thos. H. Allan, et al  
Lease Name Arthur E. Oden Well No. 1  
Office Address 1221 Union National Bank Bldg., Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 3 1955  
Application for plugging filed March 3 1955  
Application for plugging approved March 3 1955  
Plugging commenced March 3 1955  
Plugging completed March 3 1955  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation tested Conglomerata & Mississippi Depth to top 3316 Bottom 3352 Total Depth of Well 3361 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	163'	None
				5 1/2"	3319'	2657'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

3361 - 3310 Sand  
3310 - 3275 6 sacks cement  
3275 - 155 Heavy Mud  
155 - 125 Rock Bridge & 15 sacks cement  
125 - 30 Heavy Mud  
30 - Surface Rock Bridge & 5 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 11 1955  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Thos. H. Allan  
Address 1221 Union National Bank Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Thos. H. Allan (producer or owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thos. H. Allan  
1221 Union National Bank Bldg., Wichita 2, Kans.  
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of March, 1955

Ocie M Stewart  
Notary Public.

My commission expires June 14, 1958

PLUGGING  
FILED SEC LT 21 R 8W  
PAGE 103 LINE 12

15.159.00371-0000

8 5/8" @ 163' - 140 Sx Circ.  
5 1/2" @ 3319' - 75 Sx Pulled 2657'

ALLAN, HINKLE, ET AL #1 A. ODEN  
NW NW SW 1-21-8W  
Rice County, Kansas  
COMM: 2/18/55 COMPL: 3/3/55  
CONTRACTOR: Tom Allan  
ELEV. 1645 RB

I.P. D & A

All Depths From Rotary Bushings

0 - 20 Soil  
 90 Sand  
 163 Red Beds  
 500 Red Shale  
 700 Shale  
 1000 Salt & Shale  
 1300 Anhydrite & Shale  
 2400 Shale & Shells  
 2750 Lime & Shale partings  
 2888 Shale and Sandy Shale  
 2894 Lime Brown  
 2915 Shale  
 2940 Lime  
 2948 Shale  
 2957 Oolitic Lime  
 3030 Lime  
 3037 Oolitic Lime  
 3180 Lime  
 3220 Lime & red sh. partings  
 3226 Lime, V.S.S. Oil  
 3243 Lime  
 3294 Shale & Lime streaks  
 3300 Lime with orange Chert  
 3316 Varicolor Shale  
 3320 Varicolor Oolitic Chert  
 with S. S. Oil  
 Ran 5 1/2" Casing to 3319  
 CHANGED TO CABLE TOOLS  
 3340 Weathered & Vitrious dark  
 tan Chert and red & green  
 Shale partings  
 3352 White Tripoli and Vit. Chert  
 S. S. Oil  
 3361 (T.D.) Red and green Shale

FORMATIONS:

2888 Top of Brown Lime  
 2915 Top of Lansing  
 3316 Top of Conglomerate  
 3320 Top of Mississippi  
 3352 Top of Kinderhook

I certify that the above is a true and correct copy of the well log on the above test.

Tom Allan

Subscribed and sworn to before me this 8th day of March, 1955

Oris M. Stewart  
Notary Public

My Commission expires June 14, 1958

**PLUGGING**  
 FILE SEC L 121 R 8W  
 BOOK PAGE 103 LINE 12

FILED  
 STATE OF KANSAS  
 RICE COUNTY  
 COMMISSIONER OF REVENUE  
 DIVISION