

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-20834-00-00
Spot: SWSNWNE Sec/Twnshp/Rge: 8-33S-6E
4267 feet from S Section Line, 1894 feet from E Section Line
Lease Name: SHENEMAN Well #: 2
County: COWLEY Total Vertical Depth: 3168 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>33405</u>	<u>PROD</u>	<u>4.5</u>	<u>3168</u>		<u>100 SX</u>
Op Name: <u>ANSTINE & MUSGROVE INC.</u>	<u>SURF</u>	<u>8.625</u>	<u>200</u>		<u>140 SX</u>
Address: <u>PO BOX 391</u> <u>PONCA CITY, OK 74602</u>					

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/18/2017 8:00 AM
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.
Proposal Rcvd. from: GARY ANSTINE Company: _____ Phone: (620) 441-8165

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 05/26/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 3080', DUMP BAILED 4 SXS CEMENT ON TOP OF PLUG. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES @ 350'-351' (4 HOLES). RIH W/TUBING @ 352'. QES MIXED & PUMPED 100 SXS 60/40 POZMIX 4% GEL 2% CC. LAYED TUBING DOWN. TOPPED WELL BACK TO SURFACE W/ 75 SXS 60/40 POZMIX 4% GEL 25 CC. TAGGED @ 120', QES MIXED & PUMPED 30 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCUALTED.

Perfs:

Top	Bot	Thru	Comments
3129	3133	CSG	

Remarks: CEMENT TICKET #51983.

Plugged through: TBG

District: 02

Signed _____

Duane Krueger
(TECHNICIAN)

INVOICED
JUL 12 2017